

MAR 02 1998

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'99 FEB 17 PM 3 39

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 14N R 13W T 14NR 14W T R T R 2. Property Controlling in Section S T R S T R 3. Miscellaneous Property in Sec. S T R S T R 4. Lot No. Recorded Plat 5. Private Claims

Linda M. Brown

VOL. 2

241

Register of Deeds Stamp & File Number

Grid with columns A-L and rows 1-13. Numbers 6-12, 18-24, 30-36 are present in the grid.

I, Norman L. Ochs, in a field survey on February 6, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 19, Lincoln Township, Newaygo County, Michigan. East One Quarter Corner, Section 24, Denver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838 7" Beech S48°W 23 Links (15.18') #1 8" Beech N33°W 40 Links (26.4') #2 Newaygo County Road Commission Sheet 1/2" Iron Power Pole N22°E 117.2' #3 Fence Post S86°E 24.7' #4

George Blass R.L.S. #5489 LCRC #278 June 23, 1961 Found 5/8" Iron reinforcing Rod in gravel road North and South in line with very old fences East and West 3 feet East of centerline of road North and South from witnesses of Newaygo County Road Commission. Set 6" diameter by 5 foot long reinforced Concrete Monument 16" White Oak N05°E 186.00' #5 22" Twin Red Oak N88°E 236.15' #6 8" Triple White Cherry S10°E 110.86' #7

Norman L. Ochs R.L.S. #22439 Drawing Number 92415B Power Pole N22°E 117.65' #3 Fence Post S88°E 24.47' #4 Fence Post S88°W 33.82' #8 14" - 14" Twin Cherry S20°E 112.34' #7

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" diameter X 8" Rod over 3" diameter brass cap in 6" concrete cylinder and the centerline of the North and South road is 3.5 feet West. The fence line going East is 3 feet South and on field line going West. The condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 good condition, #5 stump, #6 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod and set a 2 1/4" X 20" Harrison cast iron monument marked "County Survey" over concrete cylinder as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole N26°E 117.55' Found spike in West side of pole. #3 Fence Post S82°E 24.54' Found spike in South side of post. #4 16" Stump N11°E 186.3' to center. #5 22" - 38" Twin Red Oak S88°E 237.68' Set spike with tag #22439 in South side of tree. #6 16" - 21" White Cherry S05°E 112.28' Middle of both trees found spike in West side of tree. #7 Fence Post S88°W 33.92' Found spike in south side of post. #8

Signed by Norman L. Ochs Date November 5, 1998


Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors

Approved by Peer Review Group on November 10, 1998

Norman L. Ochs, County Representative.

N.L.O.



Revised May 14, 1975 Revised Jan., 1983