

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS MARLENE TOOGOOD

'94 JAN 21 PM 3 28

Marlene Toogood

VOL 001 PAGE 53

Register of Deeds Stamp & File Number

For corners in

NEWAYGO

(County)

Located In:

Corner Code #/

1. Public Land Survey	T 15N	R 11W	A-1
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Norman L. Ochs, in a field survey on November 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Corner, Section 6, Norwich Twp., Newaygo County, MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. J. Hodgson 1938
 15" Maple N63°E 4 lks #1
 12" Birch S8°W 37 lks #2

Delos G. Anderson
 August 26, 1898
 Iron Cor. sproked wheel
 Stake set 2 rods South
 2 rods E for witness
 and corner of school
 ground.
 #3 Stake South 33'.
 #4 Stake East 33'.
 Book A, Pg. 231

Lyle Shepherd's Book 1916
 6" Pine Stp. N71°W 57-1/2" #5
 5" Elm N53°W 41' #6
 4" Elm N37°W 45.5' #7
 1966 NCRC Monument (2" rod)
 NW Cor School S50°E 130.4' #11
 Power Pole N45E 105.3' #12
 Fence Cor S45°W 46.6' #13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument (2" rod) of NCRC from 1966 replaced with a Harrison Monument.
 /cast iron

Condition of recorded witnesses is: #1 gone, #2 gone, #3 gone, #4 gone, #5 gone, #6 gone, #7 gone, #8 gone, #9 gone, #10 gone, #11 good condition, #12 good condition, #13 gone.

We also checked for D. Anderson's stake 2 rods South & 2 rods East. Found nothing in Centerline of a driveway.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Cast Iron Harrison Monument and is accepted as a substantial marker for the section corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

N.W. Cor. School S44°E 129.89' #11
 P.Pole N55QE 105.90' (Spike in SE side of Pole) #12
 8" Poplar S22°W 87.62' (Spike in Ease side of tree).
 Tel. Riser (Top CL) N55°W 45.50'.



Signed by Norman L. Ochs
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Date November 8, 1993

Approved By Peer Review Group Nov. 9, 1993
 Norman L. Ochs, County Representative

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							