

MAY 28 1997

COMMISSIONER

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

VOL. 2 PAGE 22

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 15N R 11W B-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5			4			3		2	
3													
4	7			6			9			10		11	12
5													
6	10			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Norman L. Ochs, in a field survey on May 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 6, Norwich Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
22" White Pine N28°E 3 Links (1.98")#1
9" Hemlock S56½°W 18 Links (11.88")#2

No subsequent restoration since G.L.O.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

I was unable to locate any monument of accessories 1 and 2 at this location. I set the corner in an East and West fence (straight) at a prorated (G.L.O. vs. measurement) position between the Southwest Corner and Southeast Corner, Section 6. This position fits a prorated distance to creek crossing East by 10 feet ±. I measured 2387.38 feet to Southwest Corner, Section 6 and 2655.62 feet to Southeast Corner, Section 6. This position is 4.9 feet North of a straight line between Section Corners.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 16" Red Pine S59°W 9.66' Spike in Southeast side of tree.
- 18" Red Pine S76°E 32.40' Spike in North side of tree.
- 12" Twin Cherry N13°W 39.48' Spike in East side of tree.
- 8" Twin Cherry N54°W 36.80' Spike in Southwest side of tree.

Signed by *Norman L. Ochs* Date September 12, 1996
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.

N.L.O.

