

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

'97 FEB 12 PM 4 45

*Linda M. Brown*

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N R11W</u> T <u>16N R11W</u> T _____ T _____	<u>C-13</u> ✓ _____ _____
2. Property Controlling in Section	S _____ S _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ S _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

PAGE

23

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12							
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Norman L. Ochs, in a field survey on May 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Northeast Corner, Section 6, Norwich Township, Newaygo County, Michigan  
Southeast Corner, Section 31, Barton Township, Newaygo County, Michigan

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. John Hodgson 1838  
11" Beech S41°W 43 Links (28.38') #1  
7" Cedar S28°E 26 Links (17.16') #2

Delos G. Anderson (County Surveyor)  
1898 Reported distance of 2624.16' West to North One Quarter Corner, Section 6

Duane F. Wood L.S. #24625 1988  
Set 1/2" Rod in intersection of roads at split of right-of-way fences LCRC #829  
Triple Cedar AZ 163° 58.8' #3  
6" Birch AZ 205° 69.2' #4  
8" Poplar AZ 320° 46.4' #5

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

I found Duane F. Wood's 1/2" Rebar and accessories 4 and 5 that fit the corner. I measured 2643.21 feet West to the North One Quarter Corner of Section 6 and 2635.12 feet South to the East One Quarter Corner, Section 6 and 2636.95 feet East to the North One Quarter Corner of Section 5. Accessories 1, 2 and 3 were gone. Corner is in centerline of East and West gravel road and 4 feet West of centerline of road to the South.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1/2" Rod and set 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

8" White Birch S18°W 69.05' Spike in East side of tree. #4  
11" Poplar N40°W 46.60' Spike in Southwest side of tree. #5  
Power Pole S26°E 43.95' Found P.K. nail in Northeast side of pole.  
Power Pole N41°E 39.02' Found P.K. nail in Southeast side of pole.  
10" Cedar N43°W 84.46' Spike in Southwest side of tree.

Signed by Norman L. Ochs

Date September 12, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on October 24, 1996  
Norman L. Ochs, County Representative.

*N.L.O.*

