

MAY 28 1997

COMMISSIONER

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 15N R 11W C-2
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 PAGE 24

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4													
5													
6	19	20	21	22	23	24	25	26	27	28	29	30	31
7													
8													
9													
10													
11													
12													
13													

I, Norman L. Ochs, in a field survey on May 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

East One Quarter Corner, Section 6, Norwich Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
 34" White Pine N46°W 25 Links (16.5')#1
 30" Hemlock S31°E 21 Links (13.86')#2

Delos G. Anderson (County Surveyor)
 1898 Surveyed East and West One Quarter line - Reported distance of 2660.46 feet to Center One Quarter Corner, Section 6 and 5036.46 feet to the West One Quarter Corner, Section 6.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

I did not find any monument at this location. I set the corner in the center of old road bed running North and South and in line with old fence to West (that runs straight for an entire mile). From this position I measured the following distances: 2635.12 feet North to the Northeast Corner, 2659.85 feet South to the Southeast Corner, 2659.13 feet to the computed Center One Quarter Corner, and 5016.70 feet to the West One Quarter Corner.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 14" Red Pine S72°E 70.71' Spike in South Side of tree.
- 32" White Oak N64°E 59.34' Spike in North side of tree.
- 7" White Oak N23°W 26.00' Spike in West side of tree.
- 6" Cherry N88°W 40.55' Spike in South side of tree.

Signed by Norman L. Ochs Date September 12, 1996
 Norman L. Ochs
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
 Norman L. Ochs, County Representative.

N. L. O.

