

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 15N R 11W C-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property In Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2 PAGE 25

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3			●										
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Norman L. Ochs, in a field survey on May 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 6, Norwich Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
18" Yellow Pine N62°W 19 Links (12.54')#1
18" Yellow Pine S28°E 14 Links (9.24')#2

No subsequent restoration on record since G.L.O.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

I set the corner in the extension of an old road bed to the North and in line with old straight fence running West for an entire mile. I measured a distance of 5043.00 feet to the Southwest Corner of Section 6, compared to 5013 feet by G.L.O. This position fits a prorated distance (G.L.O. vs measurement) to a creek crossing to the West by 10 feet. I measured 2659.85 feet North to the East One Quarter Corner of Section 6.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

11" Red Pine N73°E 48.58' Spike in South side of tree.
8" Red Oak N68°W 31.80' Spike in South side of tree.
4" Red Oak S70°W 27.10' Spike in South side of tree.
14" Red Pine S09°W 17.75' Spike in East side of tree.

Signed by Norman L. Ochs Date September 12, 1996
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.

N.L.O.

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

