

**SURVEY &
REMONUMENTATION**
1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **129**

For corners in **COMMISSION**

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>11W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 5

Marlene Tooga

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on October 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N.W. Corner, Section 32, Norwich Twp., Newaygo Co., MI

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Milton Nye 1856	Gerald J. Gray R.L.S. #17741 1971 Set Concrete Monument
8" Beech N53°W 2 lks. (13.86') #1	18" Beech N57°W 23.5' 36" Tw. Beech S74°W 26.0'
14" Beech S50°E 29 lks. (19.14) #2	
Delos G. Anderson (Co. Surveyor)	Gerald J. Gray R.L.S. #17741 July 28, 1978 Series I, No. 9981
Book A Pages 169 and 170 July 27, 1895	Found Concrete Monument 13" Wild Cherry S15°W 39.33' #3
Measured 39.69 ch. (2619.54') from the N.W. Cor. to the N. 1/4 Cor. of Sec. 32.	10" Wild Cherry N75°W 12.55' #4 14" Wild Cherry N30°E 50.89' #5
	Measured 2637.90 feet from the N.E. Cor. to the E. 1/4 Cor. of Sec. 31 and measured 2642.12 feet from the N.E. Cor. to the N. 1/4 Cor. of Sec. 31.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On October 12, 1994, I, Norman L. Ochs, found a round concrete monument and measured 2621.49 feet from the N.W. Cor. to the N. 1/4 Cor. of Sec. 32 and condition of recorded witnesses are: #1 and #2 Gone, #3 Good Condition, #4 Gone, #5 and #6 Good Condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed round concrete monument and set a 4" dia. Harrison Cast Iron Monument 20" long stamped County Surveyor as a substantial marker for the section corner and is a careful and faithful reestablishment of the original corner.

14" Cherry S15°W 38.94' Spike in West side of tree #3
6" Cherry S85°E 23.98' Spike in South side of tree #6
15" Cherry N30°E 50.80' Spike in East side of tree #5
12" Cherry N40°W 34.97' Spike in N.E. side of tree



Signed by *Norman L. Ochs* Date November 14, 1994
Norman L. Ochs 22439
Surveyor's Michigan License No. 22439
Approved by Peer Review Group on November 10, 1994. FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
Norman L. Ochs, County Representative. *N.L.O.* REVISED MAY 14, 19
REVISED JAN., 19

A. Description....(Continued)

Duane Wood R.L.S. #24625

Dec. 3, 1987 L.C.R.C. #785

Found 4" concrete monument

16" Cherry N35°E 51.15' #5

6" Cherry S80°E 23.95' #6

16" Cherry S10°W 39.00' #3

Measured 2636.36 feet from the N.W. Cor. to the W. 1/4 Cor. of Sec. 32 and measured 2621.80 feet from the N.W. Cor. to the N. 1/4 Cor. of Sec. 32.