

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 130

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 58

Marlene Toogood
Register of Deeds Stamp & File Number

For corners in Newaygo (County) Located In: Corner Code #

1. Public Land Survey T 15N R 11W D-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	3	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N-1/4 Cor., Sec. 32, Norwich Twp., Newygo County MI

A. Description of original monument and accessories and/or subsequent restoration:
GLO In 1895 measured 39.69 chains (2619.54') from the N-1/4 cor. to the NW cor. of Sec. 32. Measured 41.16 chains (2716.56') from the N-1/4 cor. to the NE cor. of Sec. 32. Info in Book A. Pgs 169 & 170. In 1899 measured 39.18 chains (2585.88') from the S-1/4 cor. to the C-1/4 cor. of Sec. 29. Measured 41.10 chains from the S-1/4 cor. to the SE cor. of Sec. 29. Info in Book A pgs 275 & 276. -OVER-

6" Beech N-17-1/2°E 17 lks (11.22') #1
10" Beech S17°W 45 lks (29.70') #2
7/27/1895 Delos G. Anderson
Book A., Pg's 169 & 170 (Co. Surveyor)
36" P. Stp. N73-1/2°W 106 lks (69.26') #3
22" P. Stp. N31-1/4°E 64 lks (42.24') #4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
In October, 1994, I, Norman L. Ochs, fnd. 1/2" rod & cap. Replaced with 4" Harrison cast iron monument in the exact location. I measured 2621.49 feet from the NW cor. to the N-1/4 cor. of Section 32 & measured 2703.31 feet from the N-1/4 cor. to the NE cor. of Section 32.

Condition of recorded witnesses is" #1 thru #4 gone, #5 gone #6 gone, #7 and #8 good condition, #9 thru #13 good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
0/24/94 Removed 1/2" Rod & Cap and set a 4" dia. cast iron Harrison monument 20" long in exact location as a substantial marker for the Section Corner and is accepted as a careful and faithful reestablishment of the original corner.

Cherry N37°E 61.20' Spk on NW side #7
Cherry Stp. N05°E 94.59' Spk. on NW side #8
10" Cherry S05°E 50.80' Spk. on E side.
P. Pole N80°W 165.21' Spk. on S side.
Nail and tag N15°E 70.00' #10
1/2" Rod and cap (#30389) North 33.88' #9
Nail and tag N15°E 90.00' #11
Nail and tag S15°W 60.00' #12
Nail and tag S15°W 90.00' #13



Signed by Norman L. Ochs November 2, 1994

Surveyor's Michigan License No. 22439
Approved by Peer Review Group on November 10, 1994.
Norman L. Ochs, County Representative. *M.L.O.*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

JEC 07 2000

SECTION

A cont.

July 7, 1954 Ralph A. Smith RLS #3421
Field Book 52 Pg 27
Dug found old wood stake
Set 3/4" pipe.
Fe Post S+ 32.5' New Post #5
20" P. Stp N45°+E 69.6' #6
Measured 2705.25 ft. from the S-1/4
cor. to the SE cor. of Sec. 29

Duane F. Wood RLS #24625
Dec. 3, 1987

Measured 2621.80 ft. from the N-1/4 cor.
to the NW cor. of Sec. 32. Measured
2642.26 ft. from the N-1/4 cor. to the
C-1/4 cor. and measured 2703.18 ft. from
the N-1/4 cor to the NE cor. of ec. 32

July 19, 1985 Jerry Wilcox & Assoc
RLS #14102. Fnd. 3/4" gas pipe from
1954 Survey corner is 5'+ North of CL
road and in line with pine stump fence
N & S.

4" Cherry N37°E 61.02' #7
4" Cherry in clump N04°E 34.15' #8
Cor Fe Post S04°W 30.97' #5
Fence Post S60°W 59.83' #6
LCRC #638
Measured 2621.67 ft. from the N-1/4
cor. to the NW cor. of Sec. 32.
Measured 2586.80 ft. from the S-1/4
cor. to the C-1/4 cor. of Sec. 29.
Measured 2703.59 ft. from the N-1/4 cor
to the NE cor of Sec. 32.

Wm. Fries Jr. RLS #30389
1" Pipe raised with 1/2" iron & cap
#30389.
Iron & Cap #19305 AZ 00° 33.88' #9
Nail & Tag AZ 15° 70.00' #10
Nail & Tag AZ 15° 90.00' #11
Nail & Tag AZ 195° 60.00' #12
Nail & Tag AZ 195° 90.00' #13
LCRC #953

B cont.

On Oct. 1994 I, Norman L. Ochs, found 1/2" rod and cap. Replaced with 4" Harrison
cast iron mon. in the exact location. I measured 2621.49 ft. from the NW cor.
to the N-1/4 cor. of Sec. 32 and measured 2703.31 ft. from the N-1/4 cor. to the
NE cor. of Sec. 32.

Condition of recorded witnesses is: #1 thru #4 gone, #5 #6 gone, #7 & #8
good condition, #9 thru #13 good condition.

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION