

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 131

For corners in

Newaygo (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 11W	E-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 58

Marlene Toogood
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on October 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.
NE Cor., Sec. 32, Norwich Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:
GLO Milton Nye 1837 Nov. 11, 1899 Delos G; Anderson (Co. Survey)
5" Beech N11°W 15-1/2 lks (10.23') #1 Book A Pg's 275 & 276.
12" Maple N75°E 7 lks (4.62') #2 20" P. Stp S57°W 56 lks (37.62') #3
Measured 41.10 chains (2712.60 ft.) from
7/27/1895 Delos G. Anderson (Co. Surveyor) the S-1/4 cor. to the SE cor. of Sec.
Fnd. stone corner. Measured 41.16' chains 29 and measured 38.78 chains (2559.48
(2716.56') from the N-1/4 cor. to the ft.) from the SE cor. to the E-1/4 cor
NE cor. of Sec. 32. of Sec. 29.
Book A Pg's 169 & 170.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
In Oct., 1994, I, Norman L. Ochs, found 1/2" sq. iron and a 1" pipe replaced with
4" Harrison cast iron mon. in exact location. I measured 2703.31 ft. from the
N-1/4 cor. to the NE cor. of Section 32.

Condition of witnesses is: #1 thru #8 gone, #9 and #10 good condition, #11 gone,
#12 and #13 good condition, #14 and #15 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Removed 1/2" sq. iron and 1" Pipe and set 4" dia. Harrison cast iron monument
20" long as a substantial marker for the Section corner and is accepted as a
careful and faithful reestablishment of the original corner.
Spk. on N side P.Pole N15°E 167.76 #13
Spk on W side P.Pole S72°W 100.88' #10
Face of 4" steel post marker S63°E 60.06 #12.
SE cor. school N39°W 170.18 #9



Signed by Norman L. Ochs
Norman L. Ochs 22439
Surveyor's Michigan License No.

Date November 3, 1994

Approved by Peer Review Group on
Norman L. Ochs, County Representative

1994. FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION

A cont.

County Surveyor's Book
Book # unknown Pg.
30" P. Stp. N59-1/2° E 47 ft. #4
24" P. Stp. S60-1/2° E 37 ft. #5

NCRC Sheet Iron
SE Cor. School N39°W 170.2' #9
P.Pole S72°W 100.85' #10
T.Pole N47°E 51.76' #11
Measured 2646.81 ft. from the NW cor.
to the N-1/4 cor. of Sec. 33 and measured
2654.2 ft. from the NW cor. to the W-1/4
cor. of Sec. 33.

Dec. 3, 1987 Duane F. Wood RLS #24625
Measured 2703.18 ft. from the NE cor. to
the N-1/4 cor. of Sec. 32 and measured
2653.48 ft. from the NE cor. to the E-
1/4 cor. of Sec. 32.

Recorded on Survey v.
recorded in Series T, No.
5140. Also recorded in
L.C.R.C. #638.

1949 Ralph A. Smith RLS #3421
Field Book 52, Pg. 27 Gas Pipe
REA Pole S57°30' W 67.0' #6
24" Poplar N54°30' W 67.1' #7
30" Poplar N25°W 85.6' #8
Measured 2705.25 ft. from the S-1/4 cor.
to the SE cor. of Sec. 29.

July 19, 1985 Jerry L. Wilcox RLS #14102
Fd. 1/2" sq. iron rod 2 ft. W of CL road
E-W fits old witnesses of record. Re-
corded in Series T No. 5140. Old wit.
SE Cor. School N39°W 170.2' #9
P.Pole S72°W 100.85' #10
Face of 4" Steel flow line marker
S63°E 59.93' #12
P.Pole N15°E 167.74' #13
Measured 2703.18 ft. from the NE corner
to the N-1/4 cor. of Section 32.
Measured 2560.52 ft. from the SE cor. to
the E-1/4 cor. of Section 29.
Measured 2644.68 feet from the NW cor.
to the N-1/4 cor. of Sec. 33 & measured
2653.78 ft. from the NW cor. to the W-1/4
Cor. of Sec. 33.

1990 Wm. Fries Jr RLS #30389 1/2" Sq Iron
LCRC #953
P.Pole N15°E 167.74' #13
SE cor. School N39°W 170.20' #9
P.Pole S72°W 100.85' #10
Following marker S63°E 59.93' #12
Nail & tag AZ 45° 115.00' #14
Nail & tag AZ 45° 185.00- #15

SURVEY &
REMONUMENTATION
DEC 07 2000
SECTION