

**SURVEY & REMONUMENTATION**

**MAR 19 1998**

**1997 Newaygo County Remonumentation Project**

**NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN**

**'98 MAR 6 PM 12 38**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>11W</u>	<u>K-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Linda M. Brown*

**VOL. 2 137**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on August 8, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southwest Corner, Section 1, Norwich Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye Resurvey 1856  
 14" Black Ash N32½°W 16 Links (10.56')#1  
 18" Yellow Birch S53°E 27 Links (17.82')#2

William M. Jacques (County Surveyor)  
 Book B Pages 36 and 37 Book 7 Page 13  
 Stake with broken glass around.

Lyle S. Shepherd R.L.S. #503  
 April 17, 1917 Book B Pages 82 and 83  
 Book 29 Page 8 Book 37 Pages 8, 9, 10 and 11  
 Pine Root Stake - Drag tooth - Glass  
 U.S.G.S. Bench Mark S51°W 42' #3

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 1" Pipe over 1" square Iron. The centerline of road going South is 6 feet East and the centerline of the East and West road is 1.5 feet South. The condition of the recorded witnesses are: #1 and #2 gone, #3 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed 1" Pipe set a 4" diameter Harrison monument 20" long marked "County Surveyor" over 1" square Iron as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

U.S.G.S. Bench Mark S55°W 41.86' #H-31. #3  
 14" Spruce S25°W 74.45' Set spike on East side of tree.  
 6"-8" Twin Basswood S10°E 119.03' Set spike on West side of tree.  
 36" White Oak S11°W 163.28' Set spike on East side of tree.

Signed by Norman L. Ochs Date October 7, 1997

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on October 14, 1997  
 Norman L. Ochs, County Representative.

Revised May 14, 1975  
 Revised Jan., 1983

*N.L.O.*

