SURVEY & REMONUMENTATION

APR 0 4 1996

1995 Newaygo County Remonumentation Project

For corners in

Newaygo

(County)

1. Public Land Survey

COMMISSION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Corner Code #

K-9

voi 1

PAGE 194

NEWAYGO COUNTY RECUI. MARLEL:

198 FEB 21 RM 9 42

Martina Toonsol

Register of Deeds Stamp & File Number


Property Controlling in Section Miscellaneous Property in Sec.	TR TR STR STR STR STR	
4. Lot No, Reco	orded Plat	
do hereby certify that under rec points mentioned in lines 1 and therefore as required in the cur Department of the Interior, Bur Law and/or that the corner po conformance with the rules o	, in a field survey on July 24 quirements of P. A. 74, Michigan P.A. 2 above were in conformance with regrent manual of survey instructions of eau of Land Management or by a depints mentioned in lines 3, 4 and 5 of the Michigan Board of Land S blished, re-established, monumented below:	of 1970, the corner gulations and rules the United States ecree of a Court of 5 above were in urveyors or by a

Located in:

T 15N R 11W

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N.E. Corner, Section 26, Norwich Twp., Newaygo Co., MI



A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856 9" Beech N881/2°W 7Lks (4.62')#1 6" Beech S12°W 17Lks (11.22')#2

William M. Jacques (Co. Surveyor) Book 24 Pg. 26 April 21, 1912 16" Pine S69 1/2°E 151/2' #3 20" Pine N30°E 13' #4

Measured 39.85 ch (2630.10 ft) from the N. 1/4 Cor. to the N.E. Cor. of Sec. 26

NCRC Sheet Iron 24" R. Oak S01°W 19.3' #5 Pine Stp. N75°E 17.9' #7 Pine Stp. N38°E 15.7' #4 8" T. Oak \$87°E 29,6' #6

NCRC Sheet

Measured 2470.66 ft from the N. 1/2 Cor. to the N.E. Cor. of Sec. 26 and Measured 2620.20 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 26

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING **CORNER:**

Found a 11/4" iron rod that fit witnesses by William M. Jacques from 1912 and measured 2466.69 ft from the N. 1/4 Cor. to the N.E. Cor. of Sec. 26 and measured 2608.68 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 26 and the condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 fd. remains of stump, #5 and #6 good condition, #7 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 11/4" iron rod and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

28" R. Oak S08°W 20.25' Spike in East side of tree. #5 14" Tri. R. Oak S81°E 29.67 Spike in South side of tree. #6 3" R. Oak N18°W 25.42' Spike in East side of tree. 4" Maple N37°E 15,85' Spike in West side of tree.

À Doman Norman L. Ochs

Date Septmeber 11, 1995

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Approved by Peer Review Group On _ September 12, 1995 Norman L. Ochs, County Representative.

n. L. O.

