

SURVEY & REMONUMENTATION

APR 04 1996

COMMISSION

1995 Newaygo County Remonumentation Project

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

VOL. 1 PAGE 195

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

96 FEB 21 AM 9:42

Marlene Toogood

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>11W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman L. Ochs, in a field survey on July 24, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

E. 1/4 Corner, Section 26, Norwich Twp., Newaygo Co., MI

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856
8" Maple N32°E 12Lks (7.92 ft)#1
28" W. Pine S51°W 36Lks (23.76 ft)#2
Measured 39.84 ch (2629.44 ft) from the N.E. Cor. to the E. 1/4 Cor. and measured 39.55 ch (2610.30 ft) from the E. 1/4 Cor. to the S.E. Cor. of Sec. 26

William M. Jacques (Co. Surveyor)
Book 24 Pg. 26 April 21, 1912
Measured 2629.44 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 26 and
Measured 2632 ft from the E. 1/4 Cor. to the S.E. Cor. of Sec. 26

NCRC Sheet
Measured 2620.20 ft from the N.E. Cor. to the E. 1/4 Cor. of Sec. 26 and measured 2601.13 ft from the E. 1/4 Cor. to the S.E. or. of Sec. 26

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

I did not recover any corner or accessories at this location. I set the corner at the intersection of old fences (down) North, South, East and West. The position fits reasonably well with G.L.O. measurements. I measured 2608.68 ft from the N.E. Cor. to the E. 1/4 Cor. and measured 2624.42 ft from the E. 1/4 Cor. to the S.E. Cor. of Sec. 26. I think the fences are a product or result of the 1912 Jacques survey and the condition of recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 9" Maple S21°W 37.28' Spike in East side of tree.
- 14" W. Pine S07°W 36.27' Spike in West side of tree.
- 16" Maple N18°E 22.08' Spike in East side of tree.
- 12" W. Oak N62°W 74.68' Spike in North side of tree.

Signed by Norman L. Ochs Date September 11, 1995

Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975

Approved by Peer Review Group On September 12, 1995

Revised Jan., 1983

Norman L. Ochs, County Representative.

N.L.O.

