

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo Located in: _____ Corner Code # _____
(County)


1. Public Land Survey T 16N R 11W
T 15N R 11W
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



VOL. 2 PAGE 38

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1	10	9	8	7	6	5	4
3													
4	7	6	5	4	3	2	11	10	9	8	7	6	5
5													
6	18	17	16	15	14	13	22	21	20	19	18	17	16
7													
8	19	18	17	16	15	14	23	22	21	20	19	18	17
9													
10	20	19	18	17	16	15	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	33	32	31	30	29	28	27
13													

I, Norman L. Ochs, in a field survey on December 9, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 36, Barton Township, Newaygo County, Michigan
North One Quarter Corner, Section 1, Norwich Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1838
16" Beech N76°E 18 Links (11.88') #1
16" Beech N76°W 22 Links (14.52') #2
Measured 40 Chains (2640') from the Southwest Corner to the South One Quarter Corner of Section 36 and measured 40 Chains (2640') from the South One Quarter Corner to the Southeast Corner of Section 36 and measured 80 Chains (5280') from the Southwest Corner to the Southeast Corner of Section 36.

William M. Jacques (County Surveyor)
Book B Page's 36 and 37 September 12, 1908
Stone with earthenware around
Measured 39.98 Chains (2638.68') from the Northwest Corner to the North One Quarter Corner of Section 1, T15N R11W and measured 40.12 Chains (2647.92') from the North One Quarter Corner to the Northeast Corner of Section 1, T15N R11W

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing. I prorated distances of William M. Jacques 1908 survey of Section 1, T15N R11W, Norwich Township. Measured 2625.17 feet from the Southwest Corner to the South One Quarter Corner of Section 36 and measured 2634.36 feet from the South One Quarter Corner to the Southeast Corner of Section 36 and centerline of East and West road is 2.5 feet South and the condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

14"-16" Twin Maple S02°E 14.43' Set spike and tag in West side of tree.
6" White Oak N70°E 19.50' Set spike and tag in Northerly side of tree.
6" White Oak N07°W 17.98' Set spike and tag in West side of tree.
6" Elm S82°W 85.45' Set spike and tag in North side of tree.

Signed by Norman L. Ochs Date December 11, 1996
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On December 23, 1996
Norman L. Ochs, County Representative.

N.L.O.

