

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12 39

Linda M. Brown

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

VOL. 2

154


For corners in
Newaygo
(County)

Located in: Corner Code #

1. Public Land Survey T 16N R 11W
T 15N R 11W
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on October 3, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 36, Barton Township, Newaygo County, Michigan.
Northeast Corner, Section 1, Norwich Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1838
20" Beech N63°E 27 Links (17.82') #1
14" Beech S67°W 33 Links (21.78') #2

William M. Jacques (County Surveyor)
Book 7 Page 12 1908
Stone and iron with glass around stone

Gerald J. Gray R.L.S. #17741
Liber 11 Page 180 Mecosta County Records
September 15, 1985 1" X 1" Bar
Fence Post N45°E 49.25' #3
Fence Post S30°E 35.62' #4
6" Cherry S55°W 31.62' #5

James G. Knapp R.L.S. #25853
Recorded in Liber 11 Page 862, Mecosta County Register of Deeds
Found Iron

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" X 18" Rerod next to a 1" X 12" Pointed Rod next to a 1" X 1" X 14" Rod next to a 1/2" X 2" X 14" Steel cutting edge, large stone and broken glass in the centerline of the road going North. The centerline of the East and West road is 3.5 feet South. The fence line going South is 15 feet East. The condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 leaning, #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rods, Steel cutting edge and large stone and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" in the same location as 1" X 1" X 14" Rod with broken glass around it as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

12" Cherry S55°W 31.99' Found spike in Southeast side of tree and set new spike and tag over top. #5
10" Cherry S58°E Set spike and tag in North side of tree.
8" Cherry S38°E 40.95' Set spike and tag in Northeast side of tree.
8"-6" Apple N21°E 104.73' Set spike and tag in Northwest side of tree.

Signed by Norman L. Ochs Date October 7, 1997
Norman L. Ochs
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, January 28, 1971
Revised July 4, 1975
Revised July 1, 1983

Approved by Peer Review Group on December 18, 1997
Norman L. Ochs, County Representative.

N.L.O.

