

SURVEY & REMONUMENTATION

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 28 PM 1 17

SECTION

Form with fields: For corners in Newaygo (County), Located in: T 15N R 11W, Corner Code # M-7, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Linda M. Brown

VOL. 2

360

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 6-36.

I, Norman L. Ochs, in a field survey on November 5, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 24, Norwich Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- G.L.O. John Hodgson 1838 Resurvey 10" Beech S65°W 26 Links (17.16') #1 10" Beech N09°W 37 Links (24.42') #2 Lyman W. June (Mecosta County Surveyor) April 26, 1897 Field Book 2, Page 34 No Stake found - Set Post on due West course 74.68 Chains (4928.88') from Southeast corner of Section 18, T15N R10W. Lyman W. June (Mecosta County Surveyor) April 22, 24 thru 26, 1899 Field Book 3, Page 54 Stake - one Beech Stump found in place scared. Delos G. Anderson (County Surveyor) 1900 12" Maple North 20' #3 Lyman W. June (Mecosta County Surveyor) July 1, 1901 Field Book 4, Page 120 Stake at original corner. Newaygo County Road Commission Sheet 8" White Oak N12°W 26' #4 8" White Oak S32°E 41' #5

OVER

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1" x 26" Rebar on line ± with red painted trees running East and West. The centerline of old M-20 is 379.6 feet ± North. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rebar and set a 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 20" White Oak N15°W 26.00' Found spike in East side of tree. #4 18" White Oak S38°E 41.90' Found spike in East side of tree. #5 Old M-20 North 379.6' ± #6 16" - 16" Twin White Oak N66°E 29.35' Found spike in North side of tree. #7 10" Red Oak S25°W 7.7' Found spike in North side of tree.

Signed by Norman L. Ochs Date November 10, 1999 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group on December 16, 1999 Norman L. Ochs, County Representative.

M. L. O.



A. Description (cont.)

Lyle S. Shepherd R.L.S. #503

1915 to 1950 Witness Book Number 1, Page 62 and the County Surveyor's Witness Book

1" x 3' Gas Pipe

8" White Oak N12½°W 26.0' #4

8" White Oak S32°30'E 41.0' #5

E.E. Sours (Mecosta County Surveyor)

1916 Mecosta County Road Commission

1" Gas Pipe, 3 feet long, braced with stones.

Corner is S00°30'W 379.6' of road. #6

8" White Oak N12°5'W 26.0' #4

8" White Oak S32°30'E 41.0' #5

Bill Wright (Mecosta County Surveyor)

8" White Oak N12°W 26' #4

8" White Oak S32°E 41' #5

Patrick A. Salisbury R.L.S. #13594

October 23, 1973 Found 1" x 3' Pipe 6" - 8" under ground

Found 2 witnesses by Wright

Corner is 379.81 feet South of the centerline of M-20 (about half way down on the hill side)#6

12" White Oak N12°W 25.96' #4

8" - 12" Twin White Oak S32°E 41.84' #5

12" - 12" Twin Oak N64°E 29.36' #7

Jack E. Pierson R.L.S. #19305

June 29, 1976 Recorded in Series H, Number 5143 and Series I, Number 1623 (Newaygo County Records) and Liber 1, Page 260 (Mecosta Country Records.)

1" Gas Pipe had been removed. Recovered position from witnesses and placed a ½" Iron.

12" Oak N12°W 25.96' #4

8" - 12" Twin Oak S32°E 41.84' #5

12" - 12" Twin Oak N64°E 29.36' #7

Duane F. Wood R.L.S. #24625

December 5, 1986 LCRC #965

Found ½" Steel Bar

12" Oak N12°W 25.96' #4

Twin Oak S32°E 41.48' #5

Twin Oak N64°E 39.36' #7

SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION