

MAY 2 1996

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS

SURVEY & REMONUMENTATION

APR 04 1996

1995 Newaygo County Remonumentation Project

COMMISSION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

VOL. 1 PAGE 198 NEWAYGO COUNTY REGISTER OF DEEDS

1996 FEB 21 AM 9 486

Marlene Toogood

Form with fields: For corners in Newaygo (County), Located in: T 15N R 12W, Corner Code # A-9, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Norman L. Ochs, in a field survey on November 14, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

S.W. Corner, Section 19, Monroe Twp., Newaygo Co., MI S.E. Corner, Section 24, Merrill Twp., Newaygo Co., MI

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1838 9" Aspen N56°E 12Lks (7.92')#1 6" W. Oak S53°E 75Lks (49.5')#2 Lyle S. Shepherd RLS #503 Book 81 Pg. 76 1937 Measured 2631.3 ft from the E. 1/4 Cor. to the S.E. Cor. of Sec. 24, T15N R13W and measured 2644.8 ft from the S.E. Cor. to the S. 1/4 Cor. of Sec. 24, T15N R13W John C. Brewster (Co. Surveyor) Book A Pg. 123 Dec. 9, 1892 Old stake bearing stumps standing Measured 40.14 ch (2649.24 ft) from the N. 1/4 Cor. to the N.E. Cor. of Sec. 25, T15N R13W and measured 40.11 ch (2647.26 ft) from the N.E. Cor. to the E. 1/4 Cor. of Sec. 25, T15N R13W George Blass RLS #5489 1961 1 1/2" Well point 7" Tw. W. Oak N8°E 24.30' #3 8" R. Pine S36°E 32.38' #4 5" W. Pine S38°W 58.60' #5

OVER 5

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Robert A. Griffin's concrete monument with top broke off bottom of mon okay. Also fd. bottom of old 4" X 4" forest service post with tag an broken glass under conc. mon and corner is 2 ft West of centerline of trail road South and corner is in centerline of dirt road west and the condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed R.A.G.'s conc. mon and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

12" R. Pine S36°E 32.20' Set spike in East side of tree. #4 12" W. Pine S38°W 58.63' Fnd. spike in West side of tree. #5 18" R. Pine S24°E 42.90' Set spike in West side of tree. #6 10" W. Oak N60°E 33.42' Set spike in Northwest side of tree.

Signed by Norman L. Ochs Date December 12, 1995 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On December 13, 1995 Norman L. Ochs, County Representative.



A. Description (cont.)

Clinton Cole R.L.S. #17615
January 6, 1986 File Number 4468-85
2" Maple N53°E 83.19' #6
4" Twin White Oak S31°E 84.88' #7
28" Corregated Metal Pipe S62°W 30.10' #9