

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 38

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>12W</u>	<u>C-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown

VOL. 2

132

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 21, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 17, Monroe Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856	Robert L. Wetherell R.L.S. #13594
3" Spruce N17½°W 78 Links (51.48')#1	May 14, 1982 File Number 3826-82
3" Spruce S62°E 37 Links (24.42')#2	Double proportion this corner. Did not set.
	North One Quarter Corner, Section 19, S89°42'42"W 2615.25' #3
	West One Quarter Corner, Section 17, N00°14'01"W 2684.12' #4
	North One Quarter Corner, Section 20, N88°44'09"E 2615.24' #5

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found nothing. Position of corner falls in swamp. Set ¾" X 4' Pipe at Robert L. Wetherell's position. No occupation or roads found. The condition of the recorded witnesses are: #1 and #2 gone, #3 did not measure, #4 and #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set ¾" X 4' Pipe as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

West One Quarter Corner, Section 17, N00°14'01"W 2684.12' (concrete monument)#4
 North One Quarter Corner, Section 20, N88°44'09"E 2615.24' (Harrison monument)#5
 3" Jack Pine S87°E 20.25' Set spike and tag in South side of tree.
 3" Tamarack N38°E 35.73' Set spike and tag in Northwest side of tree
 4" Jack Pine N45°W 71.00' Set spike and tag in Southwest side of tree.
 4" Jack Pine N15°W 55.52' Set spike and tag in West side of tree.

Signed by Norman L. Ochs Date November 10, 1997
 Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 11, 1997 Revised May 14, 1975
 Norman L. Ochs, County Representative. Revised Jan., 1983

N.L.O.

