

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'98 MAR 6 PM 12 38

Linda M. Brown

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>12W</u>	<u>C-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

133

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 3, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 32, Monroe Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837
 28" Black Oak N17°E 25 Links (16.5') #1
 15" White Oak N24°W 30 Links (19.8') #2

Patrick A. Salisbury R.L.S. #13594
 1973 Set 5/8" Rerod by G.L.O. distance from Section Corner of 5 and 6, T14N R12W
 20" Black Oak N10°W 41.93' #3
 14" Black Oak N45°W 64.03' #4
 12" Black Oak S15°W 45.42' #5
 Northwest Corner, Section 5, T14N R12W (3/4" X 18" Pipe) East 29.04' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 3/4" X 19" Rerod in the centerline of the East and West dirt road and in line with fence going North. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 3/4" Rerod and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

26" Black Oak N07°W 41.93' Set spike and brass washer in East side of tree. #3
 20" Black Oak (with two blazes) N41°W 64.03' to centerline. #4
 18" Black Oak (blazed) S15°W 45.42' Set spike and brass washer in West side of tree above old spike mostly overgrown. #5
 Northwest Corner, Section 5, T14N R12W, 4" diameter Harrison monument East 29.05' #6
 16" Red Oak (blazed) S75°E 51.88' Set spike and brass washer in North side of tree.
 20" Red Oak (blazed) N45°E 50.75' Set spike and brass washer in West side of tree.
 10" White Oak (blazed) N14°E 26.63' Set spike and brass washer in Northeasterly side of tree.
 22" White Oak (blazed) S33°E 24.37' Set spike and brass washer in Northwesterly side of tree.

Signed by Norman L. Ochs Date December 15, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on December 18, 1997
 Norman L. Ochs, County Representative.

N.L.O.

