

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 38

SECTION

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 15N R 12W	D-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

135

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 15, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 32, Monroe Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. 8" Pine N27°E 13 Links (8.58') #1 14" Aspen N59°W 27 Links (17.82') #2	Ralph A. Smith R.L.S. #3421 Book 88 Page 21 April 17, 1958 Set ¾" Pipe 12" Black Oak S85°E 69.50' #3 4" White Oak N10°W 60.00' #4 10" Poplar S30°E 52.30' #5
Delos G. Anderson (County Surveyor) Book A Page 289 and 290 January 29, 1900 Old Corner and Witness of Government Survey found.	Newaygo Engineering and Survey Company August 23, 1977 Found ¾" Pipe North One Quarter Corner, Section 5, Wilcox Township, East 11.86' #9 Power Pole S58°E 41.13' #6 16" Black Oak N35°W 81.30' #7 8" White Oak S38°W 74.53' #8
Patrick A. Salisbury R.L.S. #13594 1973 Found ¾" X 18" Pipe Power Pole S60°E 41.13' #6 24" Black Oak N40°W 81.34' #7 6" White Oak S35°W 74.53' #8	

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ¾" Iron Pipe in centerline of gravel road going North and in centerline of gravel road going East. The centerline of gravel road going South is 5 feet East and the centerline of gravel road going West is 16 feet South. The condition of the recorded witnesses are: #1 and #2 gone, #3 and #4 stump, #5 gone, #6 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ¾" Pipe and set 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole S53°E 41.03' Found spike in North side of pole. #6
30" White Oak (blazed) N32°W 81.29' Found spike and tag #22439 in Westerly side of tree. #7
16" White Oak (blazed) S42°W 74.30' Found spike and tag #22439 in Northwesterly side of tree. #8
16" White Oak (blazed) N55°E 97.50' Found spike and tag #22439 in Northwesterly side of tree.
North One Quarter Corner, Section 5, T14N R12W, East 11.85'

Signed by Norman L. Ochs Date December 17, 1997
Norman L. Ochs
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1977
Revised May 14, 1977
Revised Jan., 1983

Approved by Peer Review Group on December 18, 1997
Norman L. Ochs, County Representative.

N.L.O.

