

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 133

For corners in

Newaygo (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 12W	E-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 58

Marlene Toogood

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on September 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.
W-1/4 Corner, Section 16, Monroe Twp., Newaygo County MI


A. Description of original monument and accessories and/or subsequent restoration:
GLO John Hodgson 1838 April 8, 1913 Lyle S. Shepherd RLS #503
10" S. Pine N3°E 50 lks (33') #1 Measured 2640 ft. from E-1/4 cor. to
7" S. Pine S20°W 22 lks (14.52') #2 NE cor. Sec. 17.
Field Book 25 Pg. 22.

Wm. M. Jacques (Co. Surveyor) 7-17-51 Ralph A. Smith RLS #3421
1910 Book 20 Pg. 3 Fnd. R.R. Rail
Measured 40.62 chains (2680.92 ft.) 24" B. Oak N42°E 50.45 #3
From the E-1/4 cor. to C-1/4 Cor. 16" W. Oak S57°E 79.09' #4
Sec. 17 SE Cor. Hse N48°W 148.43' #5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Measured 2680.3 ft. from E-1/4 Cor. to C-1/4 Cor. of Sec. 17. Field Book 88, Pg. 2.
Found railroad rail, 30" long at intersection of N & S & W roads.
Condition of accessories: #1 gone, #2 gone, #3 good, #4 Found Stump, #5 Found old foundation #6 Found stub.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced railroad rail with Newaygo County Harrison Monument* is accepted as a careful and faithful re-establishment of position of the original corner.
*4" dia. cast iron 20" long.

- 14" B. Oak N66°W 66.36' (Set 60 d. spike in NE side).
- 6" W. Oak S35°E 72.13' (Set 60 d. spike in NE side).
- 5" R. Oak S75°E 35.34' (Set 60 d. spike in N side).
- 26" B. Oak N46°E 51.42' (Found nail in SE side) #3



Signed by Norman L. Ochs Date September 29, 1994

Surveyor's Michigan License No. 22439
Approved by Peer Review Group on October 19, 1994.
Norman L. Ochs, County Representative.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION

A. cont.

1972 Newaygo Eng. & Survey Company
Fnd. R.R. Rail.
20" B. Oak N44°E 51.45' #3
14" B. Oak S46°E 80.80' #6
SE Cor. House N50°W 148.35' #5

NCRC Sheet
R.R. Rail
24" B. Oak N42°E 50.45' #3
16" W. Oak S57°E 79.09' #4
SE Cor. Hse N48°W 148.43#5

Measured 2685.65 ft. from E-1/4 Cor. to 5-1-82 Jack E. Pierson RLS #19305
C-1/4 cor. of Sec. 17. Measured 2659.04 Fnd. R.R. Rail
ft. from W-1/4 cor. to SW cor. of Sec. 16. Recorded in Series M No. 7436

7-10-73 Newaygo Eng. & Survey Co.
Found R.R. Rail.
24" B. Oak N42°E 51.48' #3
16" W. Oak S57°E 80.97' #6
SE Cor. House N48°W 148.42' #5

20" B. Oak N44°E 51.45' #3
14" B. Oak S46°E 80.89' #6
SE Cor. Hse N50°W 148.35'

Measured 2659.04 ft. from W-1/4 cor. to
SE cor. of Sec. 16.

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION