

**SURVEY &
REMONUMENTATION**

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

VOL **001** PAGE **134**
NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 58

Marlene Toogood

Register of Deeds Stamp & File Number

For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>15N</u> R <u>12W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on September 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

SW Corner, Sec. 16, Monroe Twp., Newaygo County MI
A. Description of original monument and accessories and/or subsequent restoration:

GLO John Hodgson 1838
12 S. Pine N72°E 12 lks (7.92') #1
12" S. Pine S32°W 21 lks (13.86') #2.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

(See back)-----

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" pipe (measured 2659.20' to 1/4 corner common to Sec. 16 & 17.)
Condition of accessories: #1 gone, #2 gone, #3 gone, #4 Fnd. remains of stump)
#5 found down, #6 good, #7 good, #8 good, #9 good, #10 same as #5, #11 good,
#12 good, #13 good.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 20" Long

Replaced 1-1/4" pipe with Newaygo County Monument ^{* 4" Dia. Harrison Cast Iron Mo} and is accepted as a careful and faithful reestablishment of the position of the original corner.

12 W. Oak N56°E 37.21' (Fnd. nail in NW side) #6.
22" R. Pine S63°W 84.30' (Set 60 d. spike NW side) #7.
24" B. Oak S26°E 34.97' (Fnd. nail in NE side) #8.
13" B. Oak S52°E 23.40' (Set 60d spike in SW side) #9.



Signed by Norman L. Ochs
Norman L. Ochs

Date September 29, 1994

Surveyor's Michigan License No. 22439

Approved by Peer Review Group on October 19, 1994.

Norman L. Ochs, County Representative.

A. cont.

Lyle S. Shepherd RLS #503

Witness Book

7" B. Oak S22-1/2°E 23.0' #3

7" B. Oak N79°W 46.5' #4

Forest Post East 33' #5.

7-10-73 Newaygo Eng. & Survey Co.
Fnd. 1-1/4" Pipe

10" W. Oak N56°E 37.21' #6

16" R. Pine S63°W 84.30' #7

20" B. Oak S26°E 34.97' #8

8" B. Oak S52°E 23.40' #9

Old Forest Post East 33.17'

Measured 2659.92 ft. from SW cor. to
W-1/4 cor. of Sec. 16. Measured 2663.
43 ft. from SE cor. to S-1/4 cor. Sec.
17. Measured 2666.52 ft. from SE cor.
to S-1/4 cor. of Sec. 16. and measured
2637.93 ft. from NW cor. to W-1/4 cor.
of Sec. 21.

5-1-82 Jack E. Pierson RLS #19305

Recorded in Series M No. 7436

1" Pipe

12" Oak N58°E 37.21' #11

30" Oak S27°E 34.98' #12

8" Tw. Oak S58°W 58.66' #13

Measured 2659.04 ft. from SW cor. to
W-1/4 cor. Sec. 16. Measured 2663.62
ft. from SE cor. to S-1/4 cor. Sec. 17.
Measured 2637.94 ft. from NW cor. to
W-1/4 cor. Sec. 21.