

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12 38

SECTION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>12W</u>	<u>E-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL. 2

136

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on December 5, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 32, Monroe Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1837	Newaygo Engineering and Survey Company
8" Beech N39½°E 48 Links (31.68')#1	March 24, 1977 Found ¾" Pipe
8" Beech N54°W 41 Links (27.06')#2	Northeast Corner, Section 5, T14N R12W, (¾" Pipe) East 6.61' #6
	30" Maple S09°E 19.42' #3
Ralph A. Smith R.L.S. #3421	Red Oak S82°W 35.41' #5
Book 88 Page 22 April 1958 Set ½" Pipe	Power Pole S42°W 86.95' #7
16" Twin Maple S15°E 18.50' #3	
4" White Cherry N35°W 11.20' #4	

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ¾" X 30" Iron Pipe. The centerline of the East and West gravel road is 62 feet South. The West Bank of the White River is 50 feet East. The condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 gone, #5 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Iron Pipe and set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

36" Maple (blazed) S10°E 19.35' Found spike in West side of tree. #3
24" Black Oak (blazed) S85°W 35.40' Found nail and tag #30389 in South side of tree. #5
Northeast Corner, Section 5, T14N R12W, 4" diameter Harrison monument East 6.61' #6
Power Pole S43°W 86.88' Found spike in East side of pole. #7
8"-8" Twin Cherry (blazed) N62°W 21.49' Found spike in Northerly side of tree.

Signed by Norman L. Ochs Date December 15, 1997
Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 18, 1997
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983

N.L.O.

