

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

**NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN**

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

FEB 28 PM 1 17

For corners in
Newaygo
(County)

Located in: _____ Corner Code# _____

1. Public Land Survey T 14N R 13W D-1
T 15N R 13W D-13 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

355

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13				●									

I, Norman L. Ochs, in a field survey on October 9, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 5, Lincoln Township, Newaygo County, Michigan.
South One Quarter Corner, Section 32, Merrill Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Mullett (Deputy Surveyor)
April 1, 1838
8" Beech N40°E 55 Links (36.3')#1
8" Beech N22½°W 60 Links (39.6')#2

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

No evidence of G.L.O. Post or witnesses found. No occupation or fences found. Set equal distance and on line between the Northwest Corner of Section 5 and the Northeast corner of Section 5. The centerline of gravel road going East and West is 26 feet South. The centerline of two-track going South is 70 feet East. Due to the fact that no evidence for a South One Quarter Corner was found and with common corners at the Northeast and Northwest Corners of Section 5, T14N R13W, and at the Southeast and Southwest Corners of Section 32, T15N R13W, I am also calling this position established as the South One Quarter Corner of Section 32.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as the best available evidence of the position of the corner.

40" Black Oak S51°W 56.38' Set spike and brass washer in Northwest side of tree.
6" Black Oak S55°E 10.04' Set spike and brass washer in South side of tree.
8" Black Oak N47°E 17.21' Set spike and brass washer in Northwest side of tree
10" Black Oak N32°W 23.82' Set spike and brass washer in Southwest side of tree.

Signed by Norman L. Ochs Date October 22, 1999

Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Approved by Peer Review Group on December 16, 1999
Norman L. Ochs, County Representative.

N.L.O.

