

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12 37

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

SECTION

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 15N R 13W _____ E-12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

128

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 2, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 33, Merrill Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856
16" White Pine N54°W 18 Links (11.88') #1
12" White Pine S08°E 14 Links (9.24') #2
Top of hill 40' high North 4.30 Chains (283.80') #3

Robert A. Griffin R.L.S. #13584
LCRC #577 September 11, 1980 Found 1½" X 36" angle iron by chaining South from the Northeast Corner of Section 32 a distance of 2607.33 feet from the 1908 William M. Jacques (County Surveyor) survey. Also found remains of a wood stake along side of angle iron. Found remains of G.L.O. witness stumps. Removed 1½" X 36" angle iron and replace it with a 1½" X 60" Iron pipe filled with concrete and brass cap.
8" Black Oak S43°W 7.8' #4
7" White Oak N74°W 20.30' #5
9" White Oak N70°E 6.10' #6
11" Pine Post North 1.88' #7

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1¼" Iron Pipe with brass plate. No occupation North, South, East, and West. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 1¼" Iron Pipe with brass plate as a substantial marker for the section corner and is accepted as a perpetuation of the position of the G.L.O. corner.

14" Black Oak S43°W 7.89' Found cabin spike in Northwesterly side of tree. #4
10" White Oak N74°W 20.17' Found cabin spike in South side of tree. #5
14" White Oak N70°E 6.49' Found cabin spike in South side of tree. #6
6" Post North 1.88' Found nail in East side of post. #7
16" Black Oak S42°E 21.42' Set spike and tag in West side of tree.

Signed by Norman L. Ochs Date October 7, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land and Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on November 11, 1997
Norman L. Ochs, County Representative.

N. L. O.

