

MAY 28 1967

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 15N R 13W _____ K-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 PAGE 29

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on September 9, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 36, Merrill Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856
 34" White Pine N08°W 21 Links (13.86') #1
 20" White Pine S04 1/4°E 55 Links (36.3') #2

Delos G. Anderson (County Surveyor)
 Book A Page 359 September 25, 1902
 Old Government Corner

John C. Brewster (County Surveyor)
 Book A Page 123 December 9, 1892
 Pine Root
 Both Witness Stumps standing

Robert A. Griffin R.L.S. #13584
 LCRC #158 July 6, 1967
 Found 1" X 27" pipe with broken glass around and removed and a set 5" Square Concrete Post with brass disk
 Found Stump #1
 10" White Oak S16°E137.39' #3
 5" White Pine S41°W 88.38' #4
 5" White Pine S70°W 108.84' #5
 2" White Oak N36°W 153.70' #6
 Pine Post 4"X7' North 1.0' #7

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Robert A. Griffin's concrete monument with brass disk and the centerline of the East and West road is 15 feet South and on the East edge of woods running North and South and the condition of the recorded witnesses are: #1 found remains, #2 gone, #3 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted Robert A. Griffin's concrete monument with brass disk as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Pine remains N08°W ± 13.86' #1
 14" White Oak S16°E 137.33' Found big spike in West side of tree. #3
 12" White Pine S41°W 88.38' Found spike in West side of tree. #4
 12" White Pine S70°W 108.84' Found big spike in Northwest side of tree. #5
 14" White Oak N36°W 153.84' Set spike in West side of tree. #6
 4" X 7" Pine post North 1.0' #7

Signed by Norman L. Ochs Date September 13, 1996

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 23, 1971



Approved by Peer Review Group On September 17, 1996
 Norman L. Ochs, County Representative.

Revised May 14, 1975
 Revised Jan., 1983

N.L.O.