

MAY 2 1996
COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in
Newaygo
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 15N R 13W M-11 ✓
T 15N R 12W A-11
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2 PAGE 31

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		3		2				
3													
4	7		0		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		20		21		20		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on September 17, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northeast Corner, Section 36, Merrill Township, Newaygo County, Michigan
Northwest Corner, Section 31, Monroe Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

- G.L.O. Mullett and Brookfield 1838
7" Birch S21°W 19 Links (12.54")#1
7" Birch N25°W 34 Links (22.44")#2
- John C. Brewster (County Surveyor)
Book A Page 123 December 9, 1892
Old Stake Bearing stumps standing
- Winfield S. Merrill (County Surveyor)
Book A Page's 111 & 112 1888 or 1889
Located corner from original bearing trees of Government survey
- Delos G. Anderson (County Surveyor)
Book A Page 359 September 25, 1902
22" Pine Stump N45°W 57 Links (37.62")#3
20" Pine Stump S56°E 75 Links (49.5")#4
- Lyle S. Shepherd R.L.S. #503
1 1/4" Pipe Witness Book Number 1 Page 92
2-6" Cherries N45°W 21' #5
- Robert A. Griffin R.L.S. #13584
LCRC #164 Found 1 1/4" X 36" Well Point and set a 5" Square Concrete Post with brass disk
2" Maple N53°E 83.19' #6
4" Twin White Oak S31°E 84.88' #7
4" X 7" Pine Post South 33' #8
28" Corrugated Metal Pipe South end top center S62°W 30.10' #9
28" Corrugated Metal Pipe North end top center N50°W 30.10' #10

OVER ↗

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Robert A. Griffin's concrete post with brass disk in centerline of road going East and West and right-of-way fence line going West is 10.65 feet West and 0.8 feet South of corner and the condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #10 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted Robert A. Griffin's concrete post with brass disk as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 16" Cherry (dead) N45°W 21.25' Set spike and tag in Northeast side of tree. #5
- 12" Maple N53°E 83.19' Set spike and tag in Southwest side of tree. #6
- 6"-6" Twin White Oak S31°E 84.89' Found big spike in Southwest face of tree. #7
- 4" X 7" Pine post South 33' North face of post. #8
- 28" Corrugated Metal Pipe South end top center S62°W 30.10' #9
- 28" Corrugated Metal Pipe North end top center (pipe broken) N50°W 29.27' #10

Signed by Norman L. Ochs Date October 17, 1996

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group On October 24, 1996
Norman L. Ochs, County Representative.



Revised May 14, 1975
Revised Jan., 1983

N.L.O.

A. Description (cont.)

Clinton Cole R.L.S. #17615
January 6, 1986 File Number 4468-85
2" Maple N53°E 83.19' #6
4" Twin White Oak S31°E 84.88' #7
28" Corrugated Metal Pipe S62°W 30.10' #9