

1993

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 PM 3 27

For corners in

<u>NEWAYGO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>14W</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Marlene Toogood

VOL 001 PAGE 47

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on December 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NW Corner, Sec. 6, Beaver Twp.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Milton Nye 1857	George Blass 1968 for C.P. Co. (See Drawing No. S-F17051
12" Beech N76°W 20 lks #1	Fd. 1/2" iron rod-raised w/1/2" Pipe
12" Beech S42°E 19 lks #2	10" Apple N72°W 74.08' #3
	Fe. Post N52°E 50.80' #4.
	"X" on 24" Stone S74°E 95.48' #5

Sec. 6, T15N R14W, Beaver Twp., Newaygo County, Michigan)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

George Blass found 1/2" iron rod and raised with 1/2" pipe in 1968. Honored as Section corner. I replaced with 4" cast iron Harrison Monument.

Condition of recorded witnesses is: #1, 2, 3 & 5 gone, #4 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" Harrison Cast Iron monument as a substantial marker for the Section corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

6" Tri Cherry AZ 83° 154.59'.
 Stop Sign AZ 58° 47.90'. Center of sign post.
 Fence Post AZ 328° 51.35' (Nail in West side of post) #4.
 T. Sign AZ 280° 19.94' South side of sign post.



Signed by Norman L. Ochs
 Norman L. Ochs 22439
 Surveyor's Michigan License No. _____
 Approved by Peer Review Group Dec. 21, 1993
 Norman L. Ochs, County Representative

Date December 20, 1993