

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE '00 FEB 28 PM 1 18 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 15N R 14W C-3  
 T R  
 T R  
 T R

2. Property Controlling in Section S T R  
 S T R

3. Miscellaneous Property in Sec. S T R  
 S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2

365

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 29, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 5, Beaver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856  
 15" Hemlock N22°W 12 Links (7.92')#1  
 12" Hemlock N42°E 10 Links (6.6')#2  
 24" Black Oaks S29½°E 52 Links (34.32')#3

William M. Jacques (County Surveyor)  
 November 3, 1904 Book A, Page's 391 and 392  
 Stake with broken glass around stake  
 Measured 29.60 Chains (1953.6') from the Northeast Corner to the East edge of lake, Section 7.

Delos G. Anderson (County Surveyor)  
 April 22 thru 24, 1901 Book A, Page's 321 and 322  
 Old Government Corner preserved. West fence in line. No trees there or stumps.

County Surveyor's Witness Book, Page 136  
 12" Elm N77½°W 100 Links (66')#4

Newaygo County Road Commission Sheet  
 Axle Shaft (approximate)  
 Triple Mulberry West 31.1' #5  
 Forest Post N75°W 26.1' #6  
 30" White Oak N25°E 73.8' #7

Lyle S. Shepherd R.L.S. #503  
 Witness Book Number 1, Page 112  
 Cedar Stake and glass

OVER ↘

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1¼" x 24" Axle Shaft on line ± with the centerline of bituminous road extended from the North and on line ± with the centerline of bituminous road extended East and the centerline of curve of bituminous road is N45°E 63' ±. There is no apparent occupation going South or West. The condition of the recorded witnesses are: #1 thru #7 gone, #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Axle Shaft and set a 4" diameter Harrison cast iron monument 30" long marked "County Surveyor" (set flush with grade) as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 12" - 12" - 12" - 18" Quad Black Oak S58°E 51.68' Set spike with tag #22439 in South side of tree. #8
- 6" White Pine (blazed) S09°W 76.08' Set spike with tag #22439 in West side of tree.
- 6" White Pine (blazed) N73°W 23.17' Set spike with tag #22439 in South side of tree.
- 8" - 10" - 18" Triple Red Oak S55°W 54.42' Set spike with tag #22439 in Northwest side.

Signed by Norman L. Ochs Date November 30, 1999  
 Norman L. Ochs  
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
 Revised May 13, 1975  
 Revised Jan. 1993

Approved by Peer Review Group on December 16, 1999  
 Norman L. Ochs, County Representative.

M.L.O.



A. Description (cont.)

George Blass R.L.S. #5489  
November 1968 Consumer's Power Company  
Drawing Number S-F-17051 Axle Shaft  
Mulberry N88°W 32.39' #5  
6" Oak S58°E 52.12' #8  
United States Forest Service Post N62°W 27.20' #6

Norman L. Ochs R.L.S. #22439  
August 11, 1980 Drawing Number 80072B  
Found Axle  
6" Oak S58°E 52.12' #8  
United States Forest Service Post N62°W 27.20' #6

SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION