

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA H. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 28 PM 1 18

Form with fields: For corners in Newaygo (County), Located in: T 15N R 14W, Corner Code # D-3, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Linda M. Brown

VOL. 2

366

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a circled '2' in row 3, column C.

I, Norman L. Ochs, in a field survey on November 30, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 5, Beaver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1856 16" White Pine N86 1/4°W 77 Links (50.82') #1 12" White Pine S75 1/2°W 77 Links (50.82') #2

George M. Blass R.L.S. #5489 (Consumers Power Company) Shows computed to be equal distance and on line between section corners.

Delos G. Anderson (County Surveyor) April 22 thru 24, 1901 Book A, Page's 321 and 322 Established, no trees, in crossway on South side of wagon track.

Norman L. Ochs R.L.S. #22439 July 3, 1980 Drawing Number 80072B Set 1/2" Rod on line between the Southwest Corner and the Southeast Corner (equal distance - on line) swamp on both sides of road. 5" Red Oak S76°W 122.22' #3 Poplar N57°W 84.46' #4 Corner is 0.90' South of the centerline of road. #5

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" x 18" Rerod (also pieces of wood from possible crossway) on line ± with the centerline of the East and West bituminous road and there is no North and South occupation (swamp). The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rerod and set a 2 3/4" diameter Harrison cast iron monument 20" long marked "County Survey" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 10" Red Oak (blazed) S69°W 112.12' Set spike with tag #22439 in Southeast side of tree. #3
14" Aspen (blazed) N63°W 84.46' Found spike in Southerly side of tree. #4
On line ± with the centerline of the East and West bituminous road. #5
14" Maple (blazed) N15°W 410.38' Set spike with tag #22439 in East side of tree.
30" White Pine (blazed) S64°E 202.19' Set spike with tag #22439 in South side of tree.

Signed by Norman L. Ochs Date December 10, 1999
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group on December 16, 1999 Norman L. Ochs, County Representative.

M.L.O.

