

REMONUMENTATION

MAY 2 1997

CORNER

1996 Newwaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

Linda M. Brown

Form with fields: For corners in Newwaygo (County), Located in: Corner Code#, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

VOL. 2 PAGE 33

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a black dot at row 12, column G.

I, Norman L. Ochs, in a field survey on September 6, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 34, Beaver Township, Newwaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Thomas Whelpley Resurvey 1856 12" Beech S79°E 14 Links (9.24')#1 8" Beech S35°W 24 Links (15.84')#2

NCRC Sheet Small Bolt (Approximatley) Fence Post S85°E 27. 4' #5 Fence Post S55°E 20.8' #6

William M. Jacques (County Surveyor) Book 28 Page 57 July 28, 1908 20" Pine Stump N37°30'W 69 Links (45.54')#3 20" Pine Stump S37°E 49 Links (32.34')#4

George Blass R.L.S. #5489 Consumers Power Company Section Break 1968 Found Railroad Spike Telephone Cable Marker West 35.57' #7 "X" in stone N12°W 125.15' #8 6" Maple N54°E 85.51' #9

J. Randolph Hepworth R.L.S. #26457 April 29, 1989 Job Number 89064 Found Railroad Spike and set a 1/2" Iron Buried Cable Post West 35.2' #7 10" Maple N54°E 85.56' #9

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" rod and cap #26457 and found railroad spike flat by iron on hill that has been cut and the centerline of the North and South road is 2 feet West and there is a fence going West and the condition of the recorded witnesses are: #1 thru #6 gone, #7 good condition, #8 gone, #9 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1/2" rod and cap #26457 and railroad spike and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Telephone cable marker West 34.99' #7 6" Maple N54°E 85.55' Found spike and tag in South side of tree. #9 10" Red Pine N40°W 113.39' Set spike and tag in South side of tree. 2"-10" Clump Maple S11°W 382.46' Set spike and tag in West side of tree.

Signed by Norman L. Ochs Date September 13, 1996 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group On September 17, 1996 Norman L. Ochs, County Representative.

Handwritten signature of Norman L. Ochs

