

**SURVEY & REMONUMENTATION**

MAR 19 1998

**1997 Newaygo County Remonumentation Project**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12 37

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>14W</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Linda M. Brown*

**VOL. 2**

**119**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 15, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southeast Corner, Section 3, Beaver Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye Resurvey 1857	Newaygo County Road Commission Sheet
40" White Pine N79½°E 21 Links (13.86')#1	1" Iron
14" Beech S66½°E 31 Links (20.46')#2	14" Red Pine S58°W 73.6' #4
16" Beech N65°W 52 Links (34.32')#3	12" Red Pine S08°E 67.0' #5
	Power Pole N61°E 60.1' #6

Delos G. Anderson (County Surveyor)  
Book A Page 216 September 14, 1897  
Old Government Corner

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found large amount of discolored sand, pieces of deteriorated metal, ½" X 6" Rerod (mostly deteriorated) 18" below surface, went down 4 feet and found nothing else in the centerline of the East and West bituminous road. The centerline of two-track going North is 4 feet West. The centerline of two-track going South is 15 feet West. Fence line going South is 30 feet West. The condition of the recorded witnesses are: #1 thru #3 gone, #4 dead, #5 stump, #6 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed deteriorated metals and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

18" Red Pine (dead) S60°W 73.6' to face. #4  
18" Red Pine Stump S07°E 66.6' to face. #5  
Power Pole N63°E 60.35' Set spike and tag in South side of pole. #6  
8" Red Pine (blazed) S06°E 40.42' Set spike and tag in East side of tree.  
24" Red Pine (blazed) S26°W 90.30' Set spike and tag in East side of tree.  
Power Pole N13°W 96.84' Set spike and tag in East side of pole.

Signed by Norman L. Ochs Date November 10, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 11, 1997  
Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983

*N.L.O.*

