

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

**NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN**

'98 MAR 6 PM 12 37

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>14W</u>	<u>J-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown

VOL. 2

123

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on October 15, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 2, Beaver Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye Resurvey 1857	Newaygo County Road Commission Sheet
48" Hemlock N35°W 16 Links (10.56')#1	3/4" Iron
10" Beech S16°E 12 Links (7.92')#2	Power Pole N66°W 78.4' #3
	10" Maple S10°W 87.8' #4
Delos G. Anderson (County Surveyor)	20" Maple S51°E 132.7' #5
Book A Pages 251 and 252	
May 10 and 11, 1899	
Original Corner	

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 3/4" X 21" Solid Shaft (top is 1" diameter threaded with nut) above 3/4" Rod on line with old fence going South. The centerline of the East and West bituminous road is 1.5 feet South. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 3/4" X 21" Solid Shaft and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" over 3/4" Rod as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Power Pole N63°W 78.60' Found spike in South side of pole. #3
 24" Maple (blazed) S11°W 87.80' Set spike and tag in West side of tree. #4
 36" Maple S50°E 132.70' Set spike and tag in Southwest side of tree. #5
 4" Birch N80°E 139.33' Set spike and tag in South side of tree.

Signed by Norman L. Ochs Date November 10, 1997
 Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on November 11, 1997
 Norman L. Ochs, County Representative.

N.L.O.

