

**SURVEY & REMONUMENTATION**

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

MAR 19 1998

1997 Newaygo County Remonumentation Project

'98 MAR 6 PM 12 37

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

*Linda M. Brown*

For corners in  
Newaygo  
(County)

Located in: T 15N R 14W Corner Code # K-7

1. Public Land Survey  
T 15N R 14W  
T     R      
T     R      
T     R    

2. Property Controlling in Section  
S     T     R      
S     T     R    

3. Miscellaneous Property in Sec.  
S     T     R      
S     T     R    

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2

124

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on November 13, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Northwest Corner, Section 24, Beaver Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye Resurvey 1857	Newaygo County Road Commission Sheet
10" Maple N39½°E 9 Links (5.94')#1	5" Pine Stake
18" Hemlock N68°W 20 Links (13.20')#2	4" Spruce N45°W 51.6' #6
12" White Pine S19°E 15 Links (9.90')#3	5" Spruce S40°W 35.7' #7

Lyle S. Shepherd R.L.S. #503  
July 15, 1917 Book 5 Pages 32 and 51  
40" Pine Stump N16½°E 43½ Links (28.71')#4  
20" Pine Stump S75°W 26 Links (17.16')#2

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 3" X 3" X 18" Pointed Wood Post (burnt on the pointed end) 8" below grade in the centerline of the North and South two-track. Remnants of right-of-way fences on East and West side of two track. The condition of the recorded witnesses are: #1 thru #5 gone, #6 and #7 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed pointed wood post and set a 4" Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

12" Jack Pine N37°W 51.6' to center. #6  
14" Jack Pine S50°W 35.7' to center. #7  
8" Jack Pine (blazed) N45°E 25.32' Set spike and brass washer in Westerly side of tree.  
10" Jack Pine (blazed) S80°E 31.80' Set spike and brass washer in North side of tree.  
18" Jack Pine (blazed) S22°W 62.37' Set spike and brass washer in East side of tree.  
16"-16" Twin Black Oak (blazed) S88°W 107.40' Set spike and brass washer in South side of tree.

Signed by Norman L. Ochs Date December 15, 1997  
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group on December 18, 1997  
Norman L. Ochs, County Representative.  
*N.L.O.*

