

MAR 13 2000

SECTION

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT of Act 74, Mich. P.A. 1970'00 FEB 28 PM 1 17.

For corners in
Newaygo
(County)

Located in:

Corner Code #

1. Public Land Survey

T 14N R 13W
T 14N R 14W
T 15N R 14W
T 15N R 13W

A-1
M-1
M-13 ✓
A-13

2. Property Controlling
In Section

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Linda M. Brown

VOL. 2

354

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on October 9, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- Northwest Corner, Section 6, Lincoln Township, Newaygo County, Michigan.
- Northeast Corner, Section 1, Denver Township, Newaygo County, Michigan.
- Southeast Corner, Section 36, Beaver Township, Newaygo County, Michigan.
- Southwest Corner, Section 31, Merrill Township, Newaygo County, Michigan.

	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838
9" Cedar (no bearing given) 16 Links (10.56') #1
16" Hemlock N40°E 35 Links (23.1') #2

Norman C. Caldwell R.L.S. #12018
LCRC #1124 July 1991
Placed 36" x 30" with brass cap aluminum monument.
Centerline of old two track road 3 feet below surface.
8" Maple S48°W 47.45' #3
6" Maple N56°E 39.30' #4
6" Maple S87°E 9.80' #5
Carsonite Witness Post West 7.7' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found brass cap on top of rod in the centerline of the North and South trail road. Woven fence on ground going West is 33 feet North. The condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted brass cap on top of rod as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 16" Maple S50°W 47.59' Found spike in Northwest side of tree. #3
- 10" Maple N60°E 39.37' Found spike in Southeast side of tree. #4
- 8" Maple S86°E 9.86' Found dock spike in South side of tree. #5
- Carsonite Witness Post N85°W 7.69' #6
- 6" diameter by 4 1/2" Steel Post N30°W 40.55'

Signed by Norman L. Ochs

Norman L. Ochs

Date October 22, 1999

Surveyor's Michigan License No. 22439

Approved by Peer Review Group on December 16, 1999
Norman L. Ochs, County Representative.

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
Revised May 14, 1975
Revised Jan., 1983

