

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO CO. T.
REGISTER OF DEEDS
LINDA M. BROWN

'98 MAR 6 PM 12 39

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

Linda M. Brown

For corners in
Newaygo
(County)

Located in:

Corner Code #

1. Public Land Survey

T 16N R 11W
T 16N R 12W
T _____ R _____
T _____ R _____

A-3 ✓
M-3

VOL. 2

150

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on November 28, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southwest Corner, Section 6, Barton Township, Newaygo County, Michigan.
Southeast Corner, Section 1, Home Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson October 18, 1837
7" Aspen N17°W 2.05 Chains (135.30')#1
7" Aspen N13½°E 2.07 Chains (136.62')#2

Newaygo County Road Commission Sheet
White Pine Southwest 13.0' #5
White Pine Southeast 31.0' #6

Delos G. Anderson (County Surveyor)
Book A Pages 285 and 286 January 12, 1900
Old Government Corner
Stumps of Government survey and stake found.

George H. Johnson R.L.S. #504
7" Aspen N13½°E 2.07 Chains (136.62')#3
7" Aspen N19°W 2.05 Chains (135.3')#4

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1½" X 28" Iron Pipe 12 inches above ground. The centerline of the East and West gravel road is 28 feet North. The centerline of Tower - line is 714 feet West. Found remnants of East and West fence (possible right-of-way). The condition of the recorded witnesses are: #1 thru #4 gone, #5 and #6 stump mostly decayed.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed 1½" Iron Pipe and set a 4" diameter Harrison cast iron monument 36" long, marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 8"-18" Twin Maple (blazed) S50°E 3.61' Set spike and brass washer in North side of tree.
- 14" White Pine (blazed) West 10.23' Set spike and brass washer in North side of tree.
- 16" White Pine (blazed) N69°W 51.25' Set spike and brass washer in North side of tree.
- 16" Maple (blazed) N10°E 51.18' Set spike and brass washer in East side of tree.

Signed by Norman L. Ochs

Date December 15, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on December 18, 1997
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983

N.L.O.

