

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 PM 3 29
 Marlene Toogood
 VOL 001 PAGE 71

For corners in
NEWAYGO
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>16N</u> R <u>11W</u>	A-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

SW Corner, Section 18, Barton Twp.

A. Description of original monument and accessories and/or subsequent restoration:
 A-7 (Sec. Cor. Sec's 13, 18, 19 & 24, SW Cor. Sec. 18, T16N R11W)
 1916 Lyle S. Shepherd, Field Book 36,
 G.L.O. Page 94

10" Beech S46°W 19 lks #1
 9" Beech N45°W 17 lks #2
 Lyle Shepherd's Wit. Book
 8" Pine S86°W 8.25' #3
 24" P.Stp. N32-1/4°W 50' #4

20" Pine Stp. S30-1/2°W 68' #5
 16" W. Pine Stp. N74-1/4°W 54' #6
 14" W. Pine Stp. N20-1/2°E 54-1/2' #7
 14" Y. Pine S40-1/2°E 21-3/4' #8
 14" Oak S50°W 63.07' #15
 14" Willow Stump S40°E 21.75' #16

NCRC Sheet
 8" Pine S76°W 37.5' #9
 8" Pine N19°W 50.75' #10
 24" B. Oak N25°E 38.0' #11

1982 Clayton S. Hay (LCRC #548)
 Fnd. 1/2" Rod w/sq. nut
 Fe Post E 26.67' #12
 P Pole N85°E 63.12' #13
 Gate Post N40°W 80.88' #14
 (See Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In 1916 Lyle S. Shepherd found old stake. In 1982 Clayton S Hay found 1/2" rod with square nut 8" down in gravel roadway, 8 feet + East of C.L. travel and found 1 witness.

Found 1/2" rod with square top. Replaced with 4" Harrison cast iron monument.
 Condition of recorded witnesses is: #1 thru #12 gone, #13 good cond, #14 gone, #15 good cond., #16 gone.

There is a fence going East from this corner and a fence going West that is 19 feet South of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison cast iron monument as a substantial marker for the Section corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

P. Pole N85°E 63.17' Spike in NW side of Pole. #13.
 14" R. Oak S71°W 63.14' Spike in South side of tree.
 8" R. Oak N66°W 55.70' Spike in North side of tree.
 Gate Post N25°W 81.19' Spike in East side of post.



Signed by Norman L. Ochs Date December 20, 1993
 Surveyor's Michigan License No. 22439

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Approved by Peer Group December 29, 1993
 Norman L. Ochs, County Representative

SURVEY &
 REMONUMENTATION

DEC 07 2000

SECTION

A cont.

NCRC Records

Cor. Unknown in LCRC #548

28" P. Stp. S30°W 68.00' #5

16" Pine Stp. N74°W 54.00' #16

14" P. Stp. N20°E 54.50' #7

14" Willow S40°E 21.75' #16

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION