

**SURVEY & REMONUMENTATION**

APR 04 1996

1995 Newaygo County Remonumentation Project

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

VOL. 1 PAGE 203

NEWAYGO COUNTY  
REGISTER OF DEEDS

95 FEB 21 AM 9 44

*Marilyn Toogood*

Register of Deeds Stamp & File Number

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>11W</u>	<u>B-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on May 15, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

S. 1/4 Corner, Section 18, Barton Twp., Newaygo Co., MI

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Milton Nye 1856  
6" W. Pine N33°W 5 Lks (3.3') #1  
6" W. Pine S34°E 11Lks (7.26') #2

Clayton S. Hay RLS #10688  
September 17, 1982 LCRC #549  
Set conc. monument in E & W fence line  
8" Pine post East 32.30' #3  
16" R. Pine SSW 32.78' #4  
18" R. Pine NNE 27.44' #5  
24" R. Pine Easterly 23.10' #6  
Measured 2647.92 ft from the N.W. Cor. to the N. 1/4 Corner of Sec. 19

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found concrete monument. Measured 2642.85 ft from the S.W. Cor. to the S. 1/4 Cor. of Sec. 18 and measured 2648.16 ft from the S. 1/4 Cor. to the S.E. Cor. of Sec. 18. I recovered the old Wm. Jacques (Co. Surveyor) C. 1/4 Cor. position of Sec. 18 and checked his (2) old witnesses from 1907 within less than 1 ft, using true 1/4 line intersections, therefor I feel this 1/4 Cor. must be in proper location. (see Wm. Jacques record witness book Pg. 133) and the condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted concrete monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Pine Post in fence East 32.50' Fnd. #3  
14" R. Pine S20°W 32.80' Spike in East side of tree. Fnd #4  
24" W. Pine N23°W 32.69' Spike in East side of tree. Fnd #5  
30" W. Pine East 23.09' Spike in South side of tree. Fnd #6  
18" W. Pine N45°E 31.29' Spike in East side of tree.  
18" W. Pine S56°E 45.74' Spike in North side of tree.  
20" R. Pine S69°W 49.16' Spike in North side of tree.

Signed by Norman L. Ochs Date December 12, 1995

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group On December 13, 1995  
Norman L. Ochs, County Representative.

*M.L.O.*

