

MAR 13 2000

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

1999 Newaygo County Remonumentation Project

SECTION

LAND CORNER RECORDATION CERTIFICATE '00 FEB 28 PM 1 18 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code # 1. Public Land Survey T 16N R 11W H-3 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

VOL. 2

371

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 5, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 3, Barton Township, Newaygo County, Michigan.

Grid table with columns A-M and rows 1-13. Cell (3, G) contains a circled '16'.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856 Resurvey 14" Sugar S47 1/2 E 16 Links (10.56') #1 9" Sugar N33 W 30 Links (19.8') #2

Delos G. Anderson (County Surveyor) Book A, Page's 287 and 288 January 22, 1900 Measured 40.18 Chains (2651.88') from the Southwest Corner to the South One Quarter Corner...

Robert L. Wetherell R.L.S. #24624 1978 Found Gas Pipe 2 feet below surface of gravel road. Raised to the surface with a 1/2" Rebar. 16" Locust S49 E 35.40' #3 Culvert S19 W 37.90' #4 6" Red Pine N40 E 69.63' #5

James J. Keller R.L.S. #10693 Recorded in Liber 349, Page's 1596 and 1597 August 9, 1989 Found 1/2" Rebar and cap #24624 3" deep 2" Iron Pipe Sign Post N36 W 49.3' #6 Concrete Culvert North end S19 W 37.9' #4 24" Locust S49 E 35.40' #3 8" Red Pine N40 E 69.63' #5

Robert L. Wetherell R.L.S. #24624 January 27, 1998 Found 1/2" capped Rebar #24624 Power Pole N14 E 181.0' #7 16" Elm S37 E 119.81" #8 Power Pole S70 W 126.67' #9 1/2" Capped Iron Rod N30 W 50.27' #10

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod and cap #24624 on top of a Gas Pipe in the centerline of the East and West bituminous road and the centerline of the gravel road going North is 3 feet +/- East. There is no other apparent occupation. The condition of the recorded witnesses are: #1 thru #3 gone, #4 good condition, #5 and #6 gone, #7 thru #10 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" on top of Gas Pipe as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

1' Black Culvert West end S19 W 37.15' #4 Power Pole N14 E 181.10' Set spike with tag #22439 in East side of pole. #7 18" Elm S40 E 119.90' Found spike in Northeast side of tree. #8 Power Pole S65 W 126.82' Found spike in Northerly side of pole. #9 1/2" Rod and cap #24624 N30 W 50.27' #10

Signed by Norman L. Ochs Date November 10, 1999 Surveyor's Michigan License No. 22439



Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983 Approved by Peer Review Group on November 30, 1999 Norman L. Ochs, County Representative.