

MAR 13 2000

'00 FEB 28 PM 1 18

SECTION

1999 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

Linda H. Brown

For corners in Newaygo (County) Located in: Corner Code#

1. Public Land Survey T 16N R 11W I-4  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2

375

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on July 9, 19 99, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 11, Barton Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Milton Nye 1856 Resurvey  
9" Sugar S56°E 22 Links (14.52') #1  
14" Hemlock N50°W 39 Links (25.74') #2

Delos G. Anderson (County Surveyor)  
Book A, Page's 279 and 280 January 4, 1900  
Old Government Corner Iron for corner.

Gerald J. Gray R.L.S. #17741  
1990 Steel pin found in road  
Stump S85°W 29.50' #3  
Poplar S50°E 46.5' #4  
Twin Cherry N25°W 99.95' #5

Robert L. Wetherell R.L.S. #24624  
May 25, 1994 Recorded in Liber 359, Page 8515  
6" White Pine N62°E 40.38' #6  
16" Cherry S85°W 151.45' #7  
3" Maple N42°W 78.81' #8  
5" Elm S20°E 72.80' #9

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 1/2" Rod and cap #24624 in the centerline of the North and South bituminous road. No other apparent occupation. The condition of the recorded witnesses are: #1 thru #3 gone, #4 stump, #5 thru #8 good condition, #9 stump.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed Rod and cap and set a 2 3/4" diameter Harrison cast iron monument 20" long marked "County Survey" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

Poplar Stump S50°E 46.5' Found spike. #4  
10" - 6" Twin Cherry N18°W 99.90' Found spike in East side of tree. #5  
10" White Pine N55°E 40.40' Found spike in Westerly side of tree. #6  
26" Cherry S85°W 151.42' Found spike in North side of tree. #7  
6" Maple N42°W 78.83' Found spike in Southwest side of tree. #8  
Elm Stump S20°E 72.80' Found spike. #9

Signed by Norman L. Ochs Date October 22, 1999

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 30, 1999  
Norman L. Ochs, County Representative.

Revised May 14, 1975  
Revised Jan., 1983

*N. L. Ochs*

