

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 28

For corners in

<u>NEWAYGO</u> (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>16N</u> R <u>12W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Marlene Toogood*  
VOL 001 PAGE 65

Register of Deeds Stamp & File Number

I, Norman L. Och, in a field survey on November 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West-1/4 Corner, Sec. 6, Home Twp., Newaygo County, MI<sub>13</sub>

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1837 J. Hodgson NCRC 1966  
8" Pine S41°W 32 lks #1 1" Pipe  
8" Pine N53°W 17 lks #2 8" W. Oak N55°W 60.1' #3  
8" W. Oak S58°W 53.3' #4

1966 Robert A. Griffin RLS #13584  
Set 5' x 36" conc. mon  
8" W. Oak S48°W 53.24' #4  
5" W. Oak N61°W 60.11' #5  
1" Iron Pipe East 31.00' #6  
4" x 7' Post West 33.00' #7  
Center of Mon - NE Cor., S1/2-S1/2  
NE1/4-SE1/4  
Sec. 1, T16N, R13W South 990.00' #8

3/17/1981 N.E.&S.  
See Survey recorded Series  
#L, 4285 Fnd. conc. mon.  
8" W. Oak S48°W 53.24'.  
5" Oak N61°W 60.11'.  
1" Iron Pipe East 31.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 7, 1966, Robert A. Griffin, RLS #13584 did not find evidence of the corner. He reestablished this corner equal distance (2640.00 feet) and on a straight line between the NE corner and the SE corner of Sec. 1, T16N, R13W, he places a 5" sq. reinforced conc. post 3 feet in length set 1 foot below the surface. A 3' diameter brass disk is cast flush with the top of this monument.

Found R. A. Griffin's conc. mon. in good condition.

Condition of recorded witnesses is: #1 gone, #2 gone, #3 good condition, #4 good condition, #5 good condition, #6 gone, #7 gone, #8 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted R. A. Griffin's conc. mon. as a substantial marker for the Section corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

1/2" rod & cap (#22439) West 33.03'  
12" W. Oak S48°W 53.27' (Spike in North side of tree) #4  
10" W. Oak N61°W 60.11' (Spike in NE side of tree) #5  
Wood fence post East 31.33' (Spike in South side of post).



Signed by Norman L. Ochs  
Norman L. Ochs  
Surveyor's Michigan License No. 22439

Date November 8, 1993

Approved by Peer Review Group Nov. 9, 1993  
Norman L. Ochs, County Representative