

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 29

Marlene Toogood

VOL 001 PAGE 68

Register of Deeds Stamp & File Number

For corners in

Form with fields for Newaygo (County), Located In: (T16N R12W), Corner Code # (E-4), and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column E and row 4.

I, Norman Ochs, in a field survey on December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-4 - 1/4 Corner common to Sections 8 and 9, T16N, R12W, Newaygo Co., Mi.

- List of surveyors and monuments: 1856 - Milton Nye, G.L.O.; 1949 - Lyle Sheperd, Co. Surveyor; 1979 - Gerald J. Gray, LS 17741; 1899 - Delos Anderson, Co. Surveyor; 1983 - Jack Pierson, LS 19305.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 - 1/4 Corner common to Sections 8 and 9, T16N, R12W, Newaygo Co., Mi.

I found a narrow gage railroad rail 2 feet in length and a 1-1/2"x18" strap iron along side of rail, also the remains of rotted wood stake. The rail is in the center of North and South Gravel Road and in line with fence to East. The center of the South Branch of the Pere Marquette River is 370 feet more or Less, South. Condition of the recorded witnesses are: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 - 1/4 Corner common to Sections 8 and 9, T16N, R12W, Newaygo Co., Mi.

I replaced Railroad Rail with 4" diameter Harrison monument and is a careful and faithful re-establishment of the original corner.

- Face of 17" Sq. Conc. Post (at bottom) S80°E 31.74' (#3 & #5)
P. Pole N45°W 41.05' (R.L.S. Tag 13584) (#4)
Southwesterly corner of 17" Sq. Conc. Gate Post S10°E 105.05' (#6)
28" W. Pine S28°E 103.88' (60d spike in SW side of tree)

Signed by Norman L. Ochs, LS 22439 Date DEC 21, 1993



Surveyor's Michigan License No. Approved by Peer Review Group Dec. 21, 1993 Norman Ochs, County Representative