

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 18

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 16N R 11W	A-2
	T 16N R 12W	M-2
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown

VOL. 2

369

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on October 14, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 6, Barton Township, Newaygo County, Michigan.
East One Quarter Corner, Section 1, Home Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. John Hodgson 1838
8" White Oak S61°W 32 Links (21.12')#1
18" White Oak N49°W 27 Links (17.82')#2

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

No evidence of G.L.O. post or witnesses found. Set on line with the Southwest Corner and the Northwest Corner of Section 6 and on line with remnants of the East and West fence. The centerline of Tower-line is 324 feet West. The condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

24" White Oak (blazed) S13°E 26.56' Set spike and brass washer in East side of tree.
16" Cherry (blazed) S43°W 30.73' Set spike and brass washer in North side of tree.
12" Maple (blazed) West 46.74' Set spike and brass washer in North side of tree.
16"-16" Twin White Oak (blazed) N40°E 46.15' Set spike and brass washer in Southeasterly side of tree.

Signed by *Norman L. Ochs* Date October 22, 1999
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on November 30, 1999
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983

N. L. O.

