MAY 28:1997

1996 Newaygo County Remonumentation Project

COMMISSION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO-GOUNTY REGISTER OF DEED LINDA M. BROWN

'97 FEB 12 PM 4 4

For corners in Newaygo (County)	Located in:	Corner Code#	•	Lin	da M. Br	عدد
Public Land Survey Property Controlling in Section Miscellaneous	T 16N R 13W T R T R T R S T R	F-9	vol. 2	PAGE	44	
Property in Sec.	S T R	Panie	ster of Deeds Sta	non 9 Eile	Marakan	
		<u> </u>	stel Ol Deeds Sta	mp & rile_	Number	
4. Lot No, Reco	rded Plat		A B C	DEF	витэкц	М
I, Norman L. Ochs do hereby certify that under requipoints mentioned in lines 1 and 2 therefore as required in the curre Department of the Interior, Bureclaw and/or that the corner points of the conformance with the rules of Decree of a Court of Law, establine recovered, found as expressed by	in a field survey on October 25 airements of P. A. 74, Michigan P.A. above were in conformance with rent manual of survey instructions of au of Land Management or by a fints mentioned in lines 3, 4 and the Michigan Board of Land lished, re-established, monumentations:	A. of 1970, the corner egulations and rules of the United States decree of a Court of 5 above were in Surveyors or by a ed, re-monumented,	1030	2020		3-
recorded on this			12	3233-	-343536	g
North One Quarter Corne	r, Section 28, Lilley Towns	hip, Newaygo County, Michig	gan	•		

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Thomas Whelpley Resurvey 1856 14" Jack Pine N27°W 18 Links (11.88')#1 40" White Pine South 2 Links (1.32')#2

Patrick A. Salisbury R.L.S. #13594 Witness Book Number 1 Page 160 May 18, 1967 Found 1" Pipe 16" Oak S60°W 68.5' #3 22" Black Oak S05°E 60.9' #4 8" White Pine N30°E 57.7' #5 Glen S. Hackbardt R.L.S. #25844
April 1984 LCRC #604
Found %" Pipe 5 feet North of centerline of road going East and West and on line extended with old field fence to South 10" Oak N20°W 38.3' #6
16" Oak N02°E 39.85' #7
18" Oak S20°E 66.0' #8
20" Oak S70°W 69.25' #3

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found %" Pipe 3.15 feet long and the centerline of the East and West road is 3 feet South and old fence line on ground going South is 1.5 feet East and the condition of the recorded witnesses are: #1 and #2 gone, #3 good condition, #4 32" Stump, #5 14" Stump, #6 12" Stump, #7 good condition, #8 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ¾" Pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

18" White Oak S67°W 68.89' Set spike and tag in Southeast side of 18" Red Oak N05°E 39.71' Set spike and tag in East side of tree. #7 14" White Oak S17°W 38.84' Set spike and tag in East side of tree. 5" White Pine S51°W 40.97' Set spike and tag in Southeast side of tree. 18" Black Oak N35°W 46.99' Set spike and tag in Southwest side of 20" White Oak N51°E 54.72' Set spike and tag in Southwest side of 19 Signed by	ree. tree. ree.
Norman L. Ochs	Date November 30, 1996
· · · · · · · · · · · · · · · · · · ·	•
Surveyor's Michigan License No. 22439	Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975

Approved by Peer Review Group On <u>December 23, 1996</u>
Norman L. Ochs, County Representative.

n. L. O.

NORMAN
L. OCHS
LAND
SURVEYOR
22439

evised May 14, 1975 Revised Jan., 1983