

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 21 PM 3 28

Marlene Toogood

VOL 001 PAGE 61

Register of Deeds Stamp & File Number

Form with fields: For corners in NEWAYGO (County), Located In: T 16N R 13W, Corner Code #: K-7. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

I, Norman L. Ochs, in a field survey on December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

S.E. Cor., Sec. 14, Lilley Twp.

- A. Description of original monument and accessories and/or subsequent restoration: G.L.O. John Hodgson 1837 1955 George Blass #5489, 20" Hemlock N74-1/1E 33 lks #1 1-1/4" Well Point, 12" Hemlock N67-1/2W 15 lks #2 4" R Pine (NW Cor. Plantation) S55°E 61.20' #4, 30" Maple S55°W 42 lks #3 5" Elm S37°E 65.90' #5, 5" Maple S26°W 46.80' #6, 8" W. Oak S62°W 93.10' #7, NCRC Sheet, 1-1/4" Well Point, 4" R. Pine S55°E 61.2' #4, 5" Elm S37°E 65.9' #5, 5" Maple S26°W 46.8' #6, 8" W. Oak S62°W 93.1' #7, LCRC #288

Rat Salisbury RLS #13594 June 21, 1965 S & S Field Book 54, Pg. 77. Found well point. 36" Pine Stp. N57°W 102' #8, 6" Maple S35°W 46.81' #9, P.Pole N4°W 48.55' #10, Forest Service Sign N 14.52' #11


(See Over)-----

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Nov. 1955 George Blass found 1-1/4" well point at intersection of gravel Road E & W with gravel road South, June 13, 1972 R. A. Griffin found 1-1/4" well point in the exact location. He replaced it with a conc. monument with brass disk. 12/1/93 Found cond. mon. in good condition. Raised with R. R. Spike.

Condition of recorded witnesses is: #1 gone, #2 gone, #3 gone, #4 good condition, #'s 5 - 9 gone, #10 good condition, #11 & 12 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Accepted R. A. Griffin's monument - raised with R. R. spike as a substantial marker for the corner and is accepted as a careful and faithful re-establishment of the position of the original corner.

- P. Pole N04°W 48.69' Nail in West side of Pole #10. 12" R. Pine S42°E 61.55' Spike in NE side of tree #4. 15" Maple S15°W 105.70' Spike in West side of tree. 20" W. Oak S50°W 107.82' Spike in West side of tree.



Signed by Norman L. Ochs, Surveyor's Michigan License No. 22439

Date December 20, 1993

Approved by Peer Review Group December 21, 1993 Norman L. Ochs, County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

SURVEY & REMONUMENTATION

DEC 27 2000

SECTION

A. cont.

June 13, 1972

R. A. Griffin

Fd. 1-1/4" Well Point

At rd. intersection set mon.

w/brass disk.

7" R. Pine S55°E 61.47' #4

4" x 7" Pine Post S45°E 47.69' #12

P. Pole N5°W 44.92' #10

SURVEY &  
MONUMENTATION

DEC 07 2000

SECTION