

1993

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS
PROJECT 000000
94 JAN 21 PM 3 28
Marlene Toogood

For corners in

_____ Newaygo _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16</u> N R <u>13</u> W	M-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL 001 PAGE 63

Register of Deeds Stamp & File Number

I, Norman Ochs, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Lilley Township, Newaygo County, Michigan.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 - E. 1/4 Corner, Section 13, T16N, R13W, Newaygo Co., Mi.

1837 - John Hodgson, G.L.O.

#1 6" W. Oak S25°W 30 Links

#2 8" W. Oak N9°W 14 Links

Undated Survey by

Newaygo Co. Road Comm.

Monument - Iron

No witnesses

1974 - Paul Paquette, Surveyor

Set 5"x36" Concrete Monument

#3 1/2" Pipe N2°39'41"E 33.03'

#4 P. Pole N47°E 76.07'

#5 N.W. Cor. Sec. 18, Home Twp.

N2°39'04"E 2643.05'

#6 S.W. Cor. Sec. 18, Home Twp.

S1°10'57"W 2624.23'

May 6, 1974 - Robert Griffin, LS 13584

Found and accepted Surveyor Paquette's Concrete Monument

7 1/2" Pipe N2°E 33.03'

8 P. Pole N47°E 76.07'

9 6" W. Oak S37°E 67.67'

#10 8" B. Oak S12°W 38.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 - E. 1/4 Corner, Section 13, T16N, R13W, Newaygo Co., Mi.

I found concrete monument by Paquette. I measured the distance to the SE corner of Section 18 of 2614.36 feet. OF Home Twp. Condition of the recorded witnesses are: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 - E. 1/4 Corner, Section 13, T16N, R13W, Newaygo Co., Mi.

I accepted the 5"x36" concrete monument as a substantial monument and is accepted as a careful and faithful re-establishment of the original corner.

P. Pole N47°E 76.07' (Found nail by Griffin)

8" Maple N31°W 66.91' (Set 60d spike)

10" W. Oak S57°W 69.18' (Set 60d spike)

8" W. Oak S37°E 67.70' (Found dock spike by Griffin)

12" W. Oak S4°E 47.97' (Set 60d spike)

Signed by Norman L. Ochs Date DEC 21, 1993
Norman L. Ochs LS 22439
Surveyor's Michigan License No. _____

