

1993

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT

REGISTERED DEEDS
MAR 11 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE,
Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 28

For corners in

<u>Newaygo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16</u> N R <u>13</u> W	M-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Marlene Tugood

VOL 001 PAGE 64

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman Ochs, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-7 - S.E. Corner, Section 13, T16N, R13W, Newaygo Co., Mi. (Lilley Twp.)

1856 - Re-survey, John Hodgson, G.L.O.
#1 24" Pine S66°W 10 Links
#2 8" Pine N21°W 25 Links

1902 - Delos Anderson, Co., Surveyor
Found old Gov't Corner
#3 24" Pine S66°W 10 Links (#1)
#4 8" Pine N21°W 25 Links (#2)

1939 - S. Middlebrook, USFS
Found Railroad Rail
#5 USFS Post North 2 Links

(SEE OVER FOR CONTINUATION OF "A")

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 - S.E. Corner, Section 13, T16N, R13W, Newaygo Co., Mi.

I found Surveyor Griffin's Concrete Monument. Condition of the recorded witnesses are: #1 Found remains of stump, #2 Gone, #3 Found remains of stump, #4 Gone, #5 Gone, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10 Measured 1881.8', #11 (not checked), #12 Found in good condition, #13 Found in good condition, #14 Found in good condition, #15 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-7 - S.E. Corner, Section 13, T16N, R13W, Newaygo Co., Mi.

I accepted USFS Concrete Monument as a substantial monument and is accepted as a careful and faithful perpetuation of the original corner.

- 10" Maple S71°E 25.17' (dock spike) (#12)
- 7" Maple N55°W 18.95' (OBT #6) (dock spike) (#9 & #15)
- 7" W. Oak S40°W 24.75' (dock spike) (#8 & #14)
- 17" B. Oak S25°E 7.57' (Set 60d spike) (#7)

Signed by Norman L. Ochs
Norman L. Ochs LS 22439
Surveyor's Michigan License No. _____

Date December 21, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1981
REVISED MAY 14, 1981
REVISED JAN., 1982

Approved by Peer Review Group Dec. 21, 1993
Norman Ochs, County Representative

CONTINUATION OF "A"

1955 - George Blass, LS 5489

Monument - Railroad Rail

6 14" B. Oak N30°E 23.30'

7 16" B. Oak S25°E 7.10'

8 7" W. Oak S40°W 24.75'

9 3" Maple N55°W 18.95'

#10 M.C. East side of Pettibone Lake
West 1882.58'

#11 S.E. Cor. Sec. 24 is
S1°20'22"W 5273.56'

1972 - Robert A. Griffin, LS 13584

Found Railroad Rail and replaced
with standard USFS Concrete Monument

#12 6" Maple S71°E 25.17'

#13 Pine Post South 1.3'

#14 7" W. Oak S40°W 24.75'

#15 3" Maple N55°W 18.95'