

SURVEY &  
REMONUMENTATION

MAY 28 1997

COMMISSIONER

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY  
REGISTER OF DEEDS  
LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'97 FEB 12 PM 4 45

*Linda M. Brown*

For corners in  
Newaygo  
(County)

Located in: \_\_\_\_\_ Corner Code# \_\_\_\_\_

1. Public Land Survey T 16N R 14W H-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2 PAGE 49

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		3		2				
3													
4	7		0		0		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		20		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman L. Ochs, in a field survey on September 6, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

North One Quarter Corner, Section 34, Troy Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Thomas Whelpley Resurvey 1856  
15" Aspen N75°E 8 Links (5.28') #1  
7" Beech S65°W 16 Links (10.56') #2

Robert A. Griffin R.L.S. #13584  
LCRC #568 October 13, 1983  
Recovered its position by proportional measurement and on a straight line between controlling corners.  
5" X 36" Concrete monument with brass cap  
10" Red Pine N41°E 91.92' #3  
8" Red Pine S52°W 85.88' #4  
12" Red Pine S38°E 101.00' #5  
Northeast Corner Section 34, S87°53'13"E 2598.27' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found Robert A. Griffin's concrete monument with brass cap and the centerline of the East and West road is 10 feet South and the condition of the recorded witnesses are: #1 and #2 gone, #3 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted Robert A. Griffin's concrete monument as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

10" Red Pine N41°E 91.92' Spike in Southeast side of tree. #3  
8" Red Pine S52°W 85.98' Spike in Southwest side of tree. #4  
12" Red Pine S38°E 101.03' Spike in Northeast side of tree. #5  
Northeast Corner, Section 34, East 2598.26' #6  
18" Twin Cherry N45°W 72.50' Spike in Southwest side of tree.

Signed by Norman L. Ochs Date September 13, 1996  
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971  
Revised May 14, 1975  
Revised Jan., 1983

Approved by Peer Review Group On September 17, 1996  
Norman L. Ochs, County Representative.

*N. L. O.*

