

**SURVEY & REMONUMENT**

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

**LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

*Linda M. Brown*

For corners in Newaygo (County) Located in: T 16N R 14W Corner Code # I-12

1. Public Land Survey T 16N R 14W  
 T     R      
 T     R      
 T     R    

2. Property Controlling in Section S     T     R      
 S     T     R    

3. Miscellaneous Property in Sec. S     T     R      
 S     T     R    

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

VOL. 2 PAGE 52

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4													
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Norman L. Ochs, in a field survey on August 29, 1996, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

East One Quarter Corner, Section 34, Troy Township, Newaygo County, Michigan

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. Thomas Whelpley Resurvey 1856  
 11" Beech N66°E 31 Links (20.46') #1  
 15" Beech S12°W 37 Links (24.42') #2  
 Measured 79.41 Chains (5241.06 feet) from the Northeast Corner to the Southeast Corner of Section 34

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

No fences or any type of occupation was found, therefore I set a Harrison monument halfway and on line between the Northeast Corner and the Southeast Corner of Section 34 by a computed distance, and the condition of recorded witnesses are: #1 and #2 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Set a 4" diameter Harrison cast iron monument 36" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- 16" Black Oak S65°E 17.15' Tag and nail in North side of tree.
- 12" Red Pine N40°E 51.27' Tag and nail in East side of tree
- 20" Black Oak N65°W 38.53' Tag and nail in North side of tree.
- 14" White Oak S20°E 54.72' Tag and nail in North side of tree.
- Top center "CCC" Post N60°E 48.10'
- Centerline of two-track S45°E 48'±

Signed by Norman L. Ochs Date September 13, 1996  
 Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group On September 17, 1996

Revised May 14, 1975

Norman L. Ochs, County Representative.

Revised Jan., 1983

*N.L.O.*

