

MAR 11 1999

LIBER 19296PG535

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION

17 DEC 98 3:31 P.M. RECEIPT# 51B
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL
CLERK/REGISTER OF DEEDS

DE 11 B 303075

SECTION
For corners in
Oakland (County)

Located in: Lyon Township Corner Code #

Table with 3 columns: Item description, Township (T, S), Range (R), and Corner Code #. Includes items like Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-24-98 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Bruce Antcliff, in a field survey on July 22 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Item description, Date, Name, and Monument type. Includes items like 1816 Holmes G.L.O. Set Post, 1963 N/A O.C.R.C. Sec. Cor. Ties 1 1/4" Pipe, etc.

Records indicate this corner is common with M-13, T1N, R6E; M-1, T1S, R6E; and A-1, T1S, R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 Found a Livingston County monument with a brass cap per L.C.R.C. L.S.C. #109m (Livingston County Records) 5' South of the C/L intersection of 8 Mile Road (gravel) running East and West and Dixboro Road (gravel) running North and South. The found monument checks O.C.R.C. Section Corner Ties and L.C.R.C.'s from 1963 to the present. Also checks the following witnesses:

- O.C.R.C. Sec. Corner Ties (1963) 55.23' T. Pole (m. 55.39')
L.C.R.C. L.S.C. #109m (Livingston County)
S 20° W 65.42' to Nail w/Flasher 8" Elm (m. 65.05')
N 60° W 65.04' to Nail w/Flasher 10" Pine (m. 64.77')
S 55° E 56.88' to Nail w/Flasher U.P. (m. 56.85')
N 40° E 55.43' to Nail w/Falsher U.P. (m. 55.39')

Measure North 2639.59' to A-12
Measure East 1557.31' to B-13 (G.L.O. = 1556.94')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Livingston County Monument

- PK Nail & Oakland Co. Remonumentation Tag in W'ly Side 6' High Old P. Pole N 38° E 55.39'
PK Nail & Oakland Co. Remonumentation Tag in SW Side P. Pole S 54° E 56.85'
PK Nail & Oakland Co. Remonumentation Tag in E'ly Side 8" Elm S 36° W 65.05'
PK Nail & Oakland Co. Remonumentation Tag in NE'ly Side 12" Pine N 52° W 64.77'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-10-98

EARTH TECH

Surveyor's Michigan License No. 25826

