

RECORDATION

LIBER 1929 SPC 581

1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
17 DEC 98 3:35 P.M. RECEIPT# 518
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL
CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-10-98 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

DE 17 98 3 102

For corners in

Oakland SECTION Located in: Lyon Corner Code #
(County) Township
1. Public Land Survey T 1N R 7E E-11
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

I, Bruce Antcliff, in a field survey on July 27 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11	1816	Holmes	G.L.O.	Set Post
	N/A	Hughes	Survey	N/A
	1963	N/A	O.C.R.C. Sec. Cor. Ties	Stone
	1979	Tietsma	L.C.R.C. L. 7649 P. 586	3/4" Iron Bar
	1992	Wozniak	L.C.R.C. L. 14315 P. 443	3/4" Bar
	N/A	N/A	O.C. Tax Maps	N/A
	1994	Wozniak	Andover Creek No. 1 L.230, P.13	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Found 3/4" iron bar on the C/L intersection of 9 Mile Road (gravel) running East and West and Griswold (gravel) running North and South. Checks the following witnesses:

- L.C.R.C. L. 7649 P. 586 (1979) N 40° E 64.63 Power Pole (m. 64.78')
- L.C.R.C. L. 14315 P. 443 (1992) S 40° E 37.90' Boss Eng. Cap NE Side 9" Tree (m. 37.31')
- N 70° W 108.24' Power Pole (m. 107.96')
- N 70° W 108.08' Boss Eng. Cap S Side U.P. (m. 107.96')

Measure North 2635.33' to E-10 (G.L.O. = 2640.0')(Hughes Survey = 2627.90') (Garlock (1971) = Calc. 2635.88')
Measure South 2639.75' to E-12 (G.L.O. = 2640.0')
Measure East 2657.12' to D-11 (G.L.O. = 2656.5')
Measure West 2644.80' to F-11 (G.L.O. = 2673.0') (Andover Creek No. 1 (1994) = 2644.74)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Replaced 3/4" iron bar with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25826."

- PK Nail & Oakland Co. Remonumentation Tag in SW'ly Side P. Pole N 40° E 64.78'
- PK Nail & Oakland Co. Remonumentation Tag in S Side Util. Pole N 70° W 107.96'
- PK Nail & Oakland Co. Remonumentation Tag in S'ly Side 6" Elm S 56° W 60.80'
- PK Nail & Oakland Co. Remonumentation Tag in NE Side 4' High Wood Fence Cor. Post S 36° E 38.18'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-10-98
EARTH TECH
Surveyor's Michigan License No. 25826

